

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21597-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 34-15S-29W
1870 feet from S Section Line, 2070 feet from E Section Line
Lease Name: KS5F SPEER Well #: 34-1
County: GOVE Total Vertical Depth: 4400 feet

Operator License No.: 33396

Op Name: FAIR OIL, LTD.

Address: 225 S. COLLEGE P. O. BOX 689
TYLER, TX 75710

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3802		
PROD	4.5	4398	0	315 SX CMT.
SURF	8.625	336	0	200 SX CMT.

\$ 143-00

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/21/2007 1:00 PM

Plug Co. License No.: 6454

Plug Co. Name: CHEYENNE WELL SERVICE, INC.

Proposal Rcvd. from: RODNEY THOMPSON

Company: FAIR OIL, LTD.

Phone: (903) 510-6527

Proposed Plugging Method: Ordered 150 sxs SMD cement and 200# hulls.
Plug through casing.

Plugging Proposal Received By: HERB DEINES

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 06/21/2007 2:00 PM

KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 336' w/200 sxs cement.
4 1/2" production casing set at 4398' w/315 sxs cement.
TD 4400'. PBTD 4380'. CIBP at 3802'.
Perforations at 3751' - 3756'.
Port collar at 2070' cemented with 475 sxs - cement did not circulate.
Connected to 4 1/2" production casing - pumped 125 sxs cement with 200# hulls.
Max. P.S.I. 600#. S.I.P. 600#.
Connected to 8 5/8" surface casing - pumped 5 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3811	3818		
3751	3756		

INVOICED

DATE 7-9-07
INV. NO. 2008060058

Remarks: SWIFT CEMENT COMPANY-TICKET #12049.

Plugged through: CSG

District: 04

Signed

Darrel Dipman
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

JUN 29 2007

CONSERVATION DIVISION
WICHITA, KS

JUN 22 2007

PBT

replacement card

FAIR OIL LTD
TYLER TX 75710

34-15S-29W
1870' FSL & 2070' FEL, SEC

#34-1 KSS5F SPEER

site: 6-1/2 N & 4-1/4 E OF HEALY KS

cty: GOVE

API 15-063-21597

contr: VAL ENERGY #1

field: DOWELL

opd: RICHARD SAENZ

fr date 08/02/2005 opd date 08/08/2005 drig comp 08/18/2005 card issued 12/12/2005 last revised 07/17/2006

ELV: 2611 KB, 2601 GL LOG	depth/datum
tops.....	2004 +607
ANH.....	3680 -1069
HEEB.....	3717 -1106
LANS.....	3802 -1191
PBTD.....	3870 -1359
STARK.....	4222 -1611
LABETTE.....	4357 -1746
MISS.....	4400 -1789
LTD.....	4400 -1789
RTD.....	

IP status:
 TEMP ABD, 01/13/2006
 CORR & INFO REL: 7/17/2006 - WAS OIL WELL IN ERROR;
 WAS TIGHT HOLE
 CSG: 8-5/8" 336 / 200 SX (ALT 2), 4-1/2" 4398 / 315 SX, MULTI
 STAGE COLLAR AT 2075 / 475 SX
 NO CORES.
 7 DSTS TAKEN - DETAILS NA
 TRGT ZN: LKC (OIL), PTD 4800 (MISS), MICT (9/6/2005) - CO,
 PF (LKC) 3811-3818, W / 2 SPF, AC 750 GAL (15% SGA), SWB
 LD, NON-COMMERCIAL, SET CIBP AT 3802, PF (LKC) 3751-
 3756, W / 2 SPF, AC 500 GAL (15% SGA), SWB LD, SO ?,
 SET 2-3/8" TBG AT 3711, NO PKR, POP, P NSO & 5 BWPD, SI
 - EVAL, TEMP ABD (1/13/2006) - NO OTHER INFO
 AVAILABLE - TEMP COMP 7/17/2006

COPYRIGHT 2006
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS