

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-23970-00-00
Spot: NW NESW Sec/Twnshp/Rge: 22-17S-11W
2970 feet from N Section Line, 3630 feet from E Section Line
Lease Name: HOWARD SOEKEN Well #: 3
County: BARTON Total Vertical Depth: 3324 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3325	1722	w/125 sxs cmt
SURF	8.625	610	0	w/240 sxs cmt

\$ 108.03

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/28/2007 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: GLM COMPANY Phone: (785) 483-1307

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 10% gel - 500# hulls.
Plugged thru casing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/28/2007 10:30 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded to 2860' w/5 sxs cement using a dump bailer.
Pulled casing at 1450' w/100 sxs cement with 300# hulls.
Pulled casing at 675' w/40 sxs cement with 100# hulls.
Pulled casing at 200' w/50 sxs cement - circulated to the top.

Perfs:

Top	Bot	Thru	Comments
3291	3292		
3278	3280		
3181	3185		
3150	3154		
2908	2912		

INVOICED
DATE 7-9-07
INV. NO. 2008060059

Remarks: QUALITY OILWELL CEMENTING-TICKET #1246.

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

JUL 05 2007

CONSERVATION DIVISION
WICHITA, KS


JUN 29 2007

[Handwritten initials]

WILLIAM CLAUDE PHILLIPS
 519 S. WEST STREET
 EMPORIA, KS. 66801 #3 HOWARD SOEKEN 22-17-11W
 CONTR H-30 DRILLING NW NE SW

GEOL JIM MUSGROVE CITY BARTON
 FIELD KRAFT-PRUSA

ELV 1840 KB SPD 7/7/85 CARD ISSUED 10/10/85 IP P 15 BO & 120 BWPD
 1835 GL DRLG COMP 7/13/85 ARB 3376-3379 OA



OH LOG	Top	Depth/Datum
ANH		645+1195
HEEB		2888-1048
TOR		2907-1067
DOUG		2918-1078
BR LM		2999-1159
LANS		3017-1177
ARB		3271-1431
RTD		3324-1484

API 15-009-23,970
 8 5/8" - 610 / 240SX, 5 1/2" - 3323 / 150SX
 DST (1) 2995-3076 (KC) / 45-45-45-45, SB, REC 390' GCM (60%
 M, 32% W, 8% G), SIP 695-685#, FP 91-161 / 202-249#, HP
 1704-1675#
 DST (2) 3244-78 (ARB) / 20-20-20-20, REC 10' OCM (15% OIL,
 4% W, 81% M), SIP 916-916#, FP 45-36 / 51-42#, HP 1822-
 1802#
 DST (3) 3244-84 (ARB) / TIMES NA, SB, REC 248' HOCM, 228'
 OCM, 124' OCWM, 62' VSOCW (18% OIL, 47% G), SIP 994-
 990#, FP 45-161 / 208-258#, HP 1822-1808#
 MICT - CO, PF (ARB) 1 / 3376, 1 / 3377, 1 / 3378 & 1 / 3379, AC
 500G (15% FE), SWB DWN, SO, POP, P 15 BO & 120 BWPD (GR
 37°), 8/25/85

COPYRIGHT 1985
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS