

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-205-19405-00-00
Spot: SENESE Sec/Twnshp/Rge: 12-30S-15E
1649 feet from S Section Line, 268 feet from E Section Line
Lease Name: O AND E THOMPSON Well #: OW5-12
County: WILSON Total Vertical Depth: 600 feet

Operator License No.: 33074
Op Name: DART CHEROKEE BASIN OPERATING
Address: 600 DART RD PO BOX 177
MASON, MI 48854

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2	600		
SURF	7	23		

35-

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/21/2007 8:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: TONY WILLIAMS Company: DART CHEROKEE BASIN OPERATI Phone: (620) 779-1531

Proposed Plugging Method: Run two cement strings to TD and fill from btm to top

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE
Date/Time Plugging Completed: 03/21/2007 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A one inch cement string was lowered down the inside of the 2" production pipe to 600 ft. A one inch cement string was lowered down the outside of the production pipe to 450 ft. The well was plugged from btm to top thru these cement strings. A total of 102 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

RECEIVED
KCC DISTRICT #3

JUN 18 2007 AMD

CHANUTE, KS

INVOICED
DATE 7-9-07
INV. NO. 2008060053

Remarks:

Plugged through: CSG

District: 03

Signed

Alan M. Dunning

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

JUN 25 2007

CONSERVATION DIVISION
WICHITA, KS

PPT