

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-07098-00-00
Spot: SENESEW Sec/Twnshp/Rge: 23-19S-12W
1650 feet from S Section Line, 2970 feet from E Section Line
Lease Name: WAGNER Well #: 3
County: BARTON Total Vertical Depth: 3363 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W. 93 N. PO BOX 360
VALLEY CENTER, KS 67147

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| CIBP | | 3251 | | |
| PROD | 5.5 | 3363 | 0 | 150 SX |
| SURF | 8.625 | 226 | 0 | 105 SX |

109.30

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/07/2007 12:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: DONALD W. SANDERS SR. Company: DAYSTAR PETROLEUM, INC. Phone: (620) 669-7391

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/07/2007 1:45 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perforated at 1425' and 650'.
Tied onto 5 1/2" - pumped 225 sxs 60/40 pozmix - 10% gel cement with 600# hulls.
Max. P.S.I. 400#. S.I.P. 200#.
Pumped 50 sxs cement down annulus.
Max. P.S.I. 450#. S.I.P. 300#.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3103 | 3158 | | LKC |

INVOICED
DATE 7-9-07
INV. NO. 2008060054

Remarks: COPELAND CEMENTING COMPANY.

Plugged through: CSG

District: 04

AD

Signed _____

Case Morris

(TECHNICIAN)

JUN 18 2007

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

JUN 28 2007

CONSERVATION DIVISION
WICHITA KS


pet

15-009-07098-00-00

ALADDIN & HANNUM #3 WAGNER 53 23-19-12W
 Contr. HANNUM DRILLING CO. BARTON SE NE SW / County
 E 1816 Comm. 5-8-49 Comp. 6-3-49 IP 764 30FD

| Tops | Depth | Datum |
|------|-------|--------|
| | | |
| Awk | 989 | + 887 |
| | | |
| LANS | 3104 | - 1288 |
| ARB | 3362 | - 1546 |
| T.D. | 3363 | - 1547 |

Casing
 8" 226
 5" 3363
 DST 3105-71, OP 15
 MIN, REC 750' OIL
 & GAS CUT: MUC 3220-
 65, OP 15 MIN, REC
 270' HEAVY OIL CUT
 MUC: PERF 3219-27,
 3256-61, WTR: PB
 3251: PERF 3232-47
 SWB 2 BOPH: ACID
 1000: FL 40 BOPH



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS