

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-07101-00-00
Spot: NENESW Sec/Twnshp/Rge: 23-19S-12W
2310 feet from S Section Line, 2310 feet from W Section Line
Lease Name: WAGNER TWIN Well #: 6
County: BARTON Total Vertical Depth: 3366 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W. 93 N. PO BOX 360
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3340		
PROD	5.5	3366	0	150 SX
SURF	8.625	220	0	115 SX

\$109.40

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/07/2007 2:15 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: DONALD W. SANDERS SR. Company: DAYSTAR PETROLEUM, INC. Phone: (620) 669-7391

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/07/2007 4:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Tubing ate off in well 11 joints down.
Ran 17 joints 1" pipe in well.
Circulated with 75 sxs 60/40 pozmix - 100% gel cement.
POOH. Pumped 100 sxs cement with 200# hulls down casing.
Max. P.S.I. 600#. S.I.P. 400#.
Well had been squeezed on backside.

Perfs:

Top	Bot	Thru	Comments
3314	3332		
3270	3282		
3240	3248		
3168	3174		
3149	3157		
3128	3138		LKC
3106	3112		LKC
2922	2930		TOPEKA

INVOICED

DATE 7-9-07
INV. NO. 2008060054

Remarks: COPELAND CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed [Signature]

(TECHNICIAN) RECEIVED
KANSAS CORPORATION COMMISSION

JUN 28 2007 Form CP-2/3

JUN 18 2007

CONSERVATION DIVISION
WICHITA, KS

[Handwritten initials]

ALADDIN & HANNUM #6 53 23-19-12W
 WAGNER (TWIN) APP NE NE SW
 Contr. HANNUM DRILLING CO. BARTON County
 E. 1816 Comm. Comp. 9-30-49 IP 223 BOPD PHY POT

Tops	Depth	Datum	Casing
	627		
Awh	929	+ 887 +	189 8" 220 DST 3114-82, OP 15 5" 3371 MIN, REC 660' GAS CUT MUD: SSO: DST 3230-74, OP 15 MIN REC 60' GAS CUT MUD SSO: DP 3384 300' OIH/30 MIN ACID 500 25 BO/4 HRS
LANS	3112	- 1296	
ARB	3368	- 1552	
I.D.	3384	- 1568	

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS