

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

Lease Operator: VESS OIL CORPORATION
 Address: 1700 Waterfront Parkway, Bldg. 500 Wichita, KS 67206
 Phone: (316) 682-1537 Operator License #: 5030
 Type of Well: oil Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 6/6/07 (Date)
 by: Jeff Klock (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
KC Depth to Top: 2035 Bottom: 2040 T.D. 2544
Simpson Depth to Top: 2500 Bottom: 2502 T.D. _____
Arbuckle Depth to Top: 2540 Bottom: 2541 T.D. _____

API Number: 15-015-23,709 -00-00
 Lease Name: Scully A
 Well Number: 24
 Spot Location (QQQQ): _____ - C - E/2 - SE
1320' Feet from North / South Section Line
660' Feet from East / West Section Line
 Sec. 9 Twp. 28 S. R. 04E East West
 County: Butler
 Date Well Completed: 2/28/07
 Plugging Commenced: 6/7/07
 Plugging Completed: 6/7/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
KC	sli oil and sw	2035	2040	8-5/8"	260'	none
Simpson	sli oil and sw	2500	2502	5-1/2"	2543'	1061
Arbuckle	sw	2540	2541			

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Set CIBP @ 2000'. Free point checking casing. Shot off @ 1262', not free - shot off @ 1061' free, pull it out. Run tubing to 310'
United Cement: 80 sx 60/40 pozmix 4% gel, Ticket #7903. Cellar full of cement. Duane Krueger @ KCC witnessed.

Name of Plugging Contractor: Simmons Well Service, Inc. License #: 32991 **RECEIVED KANSAS CORPORATION COMMISSION**
 Address: 6730 Satchell Creek Road, Leon, KS 67074
 Name of Party Responsible for Plugging Fees: Vess Oil Corporation **JUN 13 2007**
 State of Kansas County, Sedgwick, ss. **CONSERVATION DIVISION WICHITA, KS**
 Casey Coats

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Casey Coats
 (Address) 1700 Waterfront Parkway, Bldg. 500, Wichita, KS 67206

SUBSCRIBED and SWORN TO before me this 11th day of June 20 07
Michelle D. Henning My Commission Expires: _____
 Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT