

RECEIVED

JUN 18 2007

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

KCC WICHITA

WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

Lease Operator: LARSON OPERATING COMPANY
A DIVISION OF LARSON ENGINEERING, INC.

Address: 562 WEST STATE ROAD 4 OLMITZ, KS 67564-8561

Phone: (620) 653-7368 Operator License #: 3842

Type of Well: oil Docket #: _____
(Oil, Gas, D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 6-4-07 (Date)

by: Taylor Herman (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Viola Depth to Top: 3566' Bottom: 3569' T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-131,20-083-00-00

Lease Name: Bauman A *KCC PKT per RBDms 6/22/07*

Well Number: 1

Spot Location (QQQQ): SE - SW - NW - _____

2310 Feet from North / South Section Line

990 Feet from East / West Section Line *KCC 6/22/07*

Sec. 27 Twp. 2 S. R. 14 East West *PKT per*

County: Nemaha

Date Well Completed: 12-20-83

Plugging Commenced: 6-5-07

Plugging Completed: 6-5-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Viola	oil	0'	252'	8-5/8"	252'	0
Viola	oil	0	3884'	5-1/2"	3884'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same, depth placed from (bottom), to (top) for each plug set.

Perf 5-1/2" @ 1000' & 300'. Spotted 50 sx of 60-40 poz w/ 4% gel thru tbg @ 2250'. Pumped 50 sx 60-40 poz w/ 4% thru tbg & circ thru perfs @ 1000' to surface up 5-1/2" x 8-5/8" annulus. Pumped 50 sx 60-40 poz w/ 4% gel thru tbg & circ cmt from 300' to surface thru 5-1/2" & 8-5/8" annulus. TOH w/ tbg. Wait 30 min, pump 50 sx 60-40 poz w/ 4% gel, down 5-1/2" - circ cmt to surface thru 5-1/2" x 8-5/8" annulus. Cmt @ surface 6-5-07.

Name of Plugging Contractor: Allied Cementing Co., LLC License #: 99996 *PKT 6/22/07*

Address: P.O. Box 31, Russell, Ks 67564

Name of Party Responsible for Plugging Fees: LARSON OPERATING COMPANY, A DIVISION OF LARSON ENGINEERING, INC.

State of KANSAS County, BARTON, ss.

Kevin Wilson (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) *[Handwritten Signature]*

(Address) 562 WEST STATE ROAD 4 OLMITZ, KS 67564-8561

SUBSCRIBED and SWORN TO before me this 15th day of June 2007

[Handwritten Signature]
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]

ALLIED CEMENTING CO., INC.

33066

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Russell

DATE <u>6-5-07</u>	SEC. <u>27</u>	TWP. <u>2S</u>	RANGE <u>14E</u>	CALLED OUT	ON LOCATION	JOB START <u>11:30am</u>	JOB FINISH <u>4:00pm</u>
LEASE <u>GALEN</u>	WELL # <u>1</u>	LOCATION <u>Seneca E to V Rd 11</u>			COUNTY <u>Nemaha</u>	STATE <u>KS</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)				<u>E Into</u>			

CONTRACTOR Express Well

TYPE OF JOB Old Hole Plug

HOLE SIZE _____ T.D. _____

CASING SIZE 5/2 DEPTH _____

TUBING SIZE 2 1/2 DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER _____

CEMENT USED 200 SF

AMOUNT ORDERED 300 @ 40 40/bel

500# Halls - Did not use!

EQUIPMENT

PUMP TRUCK CEMENTER Caig

409 HELPER Arrian

BULK TRUCK

362 DRIVER Doug

BULK TRUCK

_____ DRIVER _____

COMMON	<u>120</u>	@	<u>110</u>	<u>1332.00</u>
POZMIX	<u>80</u>	@	<u>620</u>	<u>490.00</u>
GEL	<u>8</u>	@	<u>165</u>	<u>133.20</u>
CHLORIDE		@		
ASC		@		
RECEIVED				
JUN 18 2007				
KCC WICHITA				
HANDLING	<u>312</u>	@	<u>190</u>	<u>592.80</u>
MILEAGE	<u>9¢/sk/mile</u>			<u>322.20</u>
TOTAL				<u>5183.20</u>

REMARKS:

1st Plug 2250 50 SK

2nd 1000 50 SK

3rd 300 50 SK Circulate

Mix 305 down 5/2 Cement!!

Thanks!

CHARGE TO: Carson Operating

STREET _____

CITY _____ STATE _____ ZIP _____

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____ 815.00

EXTRA FOOTAGE _____ @ _____

MILEAGE 115 @ 600 690.00

MANIFOLD _____ @ _____

TOTAL 1505.00

PLUG & FLOAT EQUIPMENT

_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
TOTAL _____		
TAX _____		
TOTAL CHARGE _____		
DISCOUNT _____	IF PAID IN 30 DAYS	

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE [Signature]

PRINTED NAME _____