

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

Lease Operator: Pioneer Exploration, Ltd
 Address: 15603 Kuykendahl, Suite 200, Houston, TX 77090
 Phone: (281) 893-9400 ext 256 Operator License #: 32825
 Type of Well: Oil and Gas Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: December 22, 2006 (Date)
 by: Doug Lewis (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Mississippi Depth to Top: 4348 Bottom: _____ T.D. 4462
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-095-21932-00-00
 Lease Name: Ethel Westerman
 Well Number: 1-33
 Spot Location (QQQQ): C - NW - NE - SW
2310 Feet from North / South Section Line
1650 Feet from East / West Section Line
 Sec. 33 Twp. 30 S. R. 9 East West
 County: Kingman
 Date Well Completed: 01/18/05
 Plugging Commenced: 04/12/07
 Plugging Completed: 04/17/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Mississippi	Oil, Gas, and Water					
				8 5/8	255	0
				4 1/2	4442	3060

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Blew gas off casing. Pulled 139 jts of tubing, pulled slips, had 20" stretch, sand at 4300', bailed 4 sacks cement, ripped casing at 3280', worked pipe, ripped casing at 3060', worked pipe free, pulled casing up to 1500', pumped 35 sack, pulled up to 900', pumped 35 sacks, pulled up to 310', circulated with 100 sacks, pulled rest of casing

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925
 Address: 190 US Highway 56, Ellinwood, KS 67526

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: Pioneer, Exploration, Ltd.

JUN 22 2007

State of Texas County, Harris, ss.

CONSERVATION DIVISION
WICHITA, KS

John Houghton (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
 (Address) 15603 Kuykendahl, Suite 200, Houston, TX 77090

SUBSCRIBED and SWORN TO before me this 21 day of June, 20 07

[Signature] My Commission Expires: 11-9-07
 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

ANITA ROMOSER
MY COMMISSION EXPIRES
November 9, 2007