

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-21343-00-01  
Spot: S2SWNW Sec/Twnshp/Rge: 7-23S-11W  
2970 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: FSI Well #: 3  
County: STAFFORD Total Vertical Depth: 3697 feet

Operator License No.: 31327  
Op Name: PAULEY, GARY DBA PAULEY OIL  
Address: PO BOX 163  
HOLYROOD, KS 67450

| String | Size  | Depth (ft) | Pulled (ft) | Comment       |
|--------|-------|------------|-------------|---------------|
| CIBP   |       | 650        |             |               |
| CIBP   |       | 3250       |             | WITH 2 SX CMT |
| PROD   | 4.5   | 3690       | 0           |               |
| SURF   | 8.625 | 488        |             |               |

*\$ 120.15*

Well Type: EOR UIC Docket No: E27089.1 Date/Time to Plug: 06/06/2007 9:25 AM  
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.  
Proposal Rcvd. from: GARY PAULEY Company: GARY PAULEY Phone:

Proposed Plugging Method: CIBP @ 3250' WITH 2 SX CMT. CIBP @ 600'. TEST CASING INTEGRITY ABOVE 600'. PERFORATE AT 625'. RUN TUBIN G& FILL 4 1/2" X 8 5/8" ANNULUS WITH CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/06/2007 10:00 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 3250' & 2 SX CMT. SET CIBP @ 650'. PERFORATED AT 600'. TEST 4 1/2" TO 300 PSIG EARLIER. PUMPED 200 SX CMT DOWN 4 1/2" CIRCULATING CEMENT TO SURFACE UP 8 5/8' X 4 1/2" ANNULUS.

Perfs:


| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3547 | 3550 |      |          |
| 3500 | 3504 |      |          |
| 3474 | 3480 |      |          |
| 3365 | 3368 |      |          |

INVOICED  
DATE 7-2-07  
INV. NO. 2008060011

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND.

Plugged through: CSG

District: 01



Signed Richard W. Lacey

(TECHNICIAN) RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 19 2007 Form CP-2/3  
CONSERVATION DIVISION  
WICHITA, KS

*PKT*  
*[Signature]*