

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-20962-00-00  
Spot: S2SWSE Sec/Twnshp/Rge: 27-18S-10W  
330 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: DOHRMAN Well #: 1  
County: RICE Total Vertical Depth: 3308 feet

Operator License No.: 8653  
Op Name: PETROLEUM TECHNOLOGIES, INC.  
Address: 801 W. 47TH ST STE 412  
KANSAS CITY, MO 64112

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3304		
SURF	8.625	275		

\$107.51

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MILE'S TESTING & SALVAGE, INC. Phone: (620) 938-2043

Proposed SEE BELOW  
Plugging  
Method:

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/14/2007 5:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND PERFS TO 3200' AND CAP WITH 5 SX'S CEMENT, CUT OFF CASING @1500'  
AND PULL TO 1200' AND PUMP 35 SX'S CEMENT WITH 100#'S COTTON HULLS,  
PULL CASING TO 850' AND PUMP 35 SX'S CEMENT WITH 100#'S COTTON HULLS,  
PULL CASING TO 325' AND CIRCULATE CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3251	3252		

INVOICED

DATE 7-2-07

INV. NO. 2008060012

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #C031780

Plugged through: CSG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION CP-2/3

JUN 19 2007

CONSERVATION DIVISION  
WICHT: KS

PKT