

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-20966-00-00  
Spot: SWSWSW Sec/Twnshp/Rge: 20-20S-10W  
633 feet from S Section Line, 4745 feet from E Section Line  
Lease Name: SMITH A Well #: 1  
County: RICE Total Vertical Depth: 3290 feet

Operator License No.: 8653  
Op Name: PETROLEUM TECHNOLOGIES, INC.  
Address: 801 W. 47TH ST STE 412  
KANSAS CITY, MO 64112

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3286		150 SX CMT.
SURF	8.625	220		125 SX CMT. <b>\$ 106.93</b>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/12/2007 2:30 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: NONE  
Date/Time Plugging Completed: 06/12/2007 4:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND OPEN HOLE TO 3230' AND CAP WITH 5 SX'S CEMENT, CUT OFF CASING @ 1700' AND PULL TO 1300' AND PUMP 35 SX'S CEMENT, PULL CASING TO 900' AND PUMP 35 SX'S CEMENT, PULL CASING TO 270' AND CIRCULATE CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3286	3290		

**INVOICED**  
DATE 7-2-07  
INV. NO. 2008060012

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET 331824

Plugged through: CSG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION P-2/3

JUN 19 2007

CONSERVATION DIVISION  
WICHITA, KS

*Handwritten initials*