

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21896-00-00
Spot: E2E2NW Sec/Twnshp/Rge: 30-30S-9W
1320 feet from N Section Line, 2310 feet from W Section Line
Lease Name: DIRKS M Well #: 1-30
County: KINGMAN Total Vertical Depth: 4392 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E. CENTRAL, SUITE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment	Per operator
PROD	4.5	4391	<u>3060</u>	125 SX	<u>Per operator</u>
SURF	8.625	239		225 SX	<u>Kcc PET</u>
T1	2.375	4382			

Well Type: OG UIC Docket No: _____ Date/Time to Plug: \$ 142.74
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 532-9232

Proposed Plugging Method: AS KCC REQUIRES.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 04/06/2007 9:45 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

PERFS WERE COVERED WITH SAND FROM 4387' TO 4330' AND CAPPED WITH 4 SKS OF CEMENT. CASING WAS RECOVERED FROM 3060' AND PULLED TO 1500' WHERE 35 SKS OF CEMENT WAS SPOTTED. CASING WAS PULLED TO 900' WHERE 35 SKS OF CEMENT WAS SPOTTED. CASING WAS PULLED TO 290' WHERE CEMENT WAS CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4380	4386		MISS


INVOICED
DATE 7-2-07
INV. NO. 2008060004

Remarks: UNTIED CEMENTING CO. TICKET # 7685 CEMENT 60/40POZMIX 4 % GEL

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

JUN 19 2007

CONSERVATION DIVISION
WICHITA, KS

PET