

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21717-00-00
Spot: SESWNW Sec/Twnshp/Rge: 26-19S-28W
3146 feet from S Section Line, 4290 feet from E Section Line
Lease Name: GARY SHAPLAND Well #: 1
County: LANE Total Vertical Depth: 4670 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E. CENTRAL, SUITE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4300		WITH 2 SX CMT
PC		2074		WITH 500 SX CMT
PROD	4.5	4668		WITH 200 SX CMT
SURF	8.625	266		WITH 175 SX CMT

\$ 151.78

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/08/2007 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: CALVIN MIKKELSON Company: MCCOY PETROLEUM Phone: (316) 636-2737

Proposed Plugging Method: CIBP @ 4300' WITH 2 SX CMT. PULL TUBNG TO 2200' & 25 SX CMT. PULL TO 1300' WITH 75 SX CMT. HOOK UP TO 4 1/2" X 8 5/8" AND ATTEMPT TO FILL.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/08/2007 11:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

CIBP @ 4300' WITH 2 SX CMT. RUN TUBING TO 2200' & PUMPED 25 SX CMT. PULLED TUBING TO 1300' & PUMPED 75 SX CMT. CMT CIRCULATED. PULLE TUBING & TOPPED OFF WITH 10 SX CMT. TIED ONTO BACKSIDE & PRESSURED TO 500# & HELD.

Perfs:


Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

INVOICED

DATE 7-2-07
INV. NO. 2008060004

District: 01



Signed

Michael J. Maier

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 19 2007

CONSERVATION DIVISION
WICHITA, KS

Form CP 2/3