

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-21423-00-00  
Spot: SWNWNE Sec/Twnshp/Rge: 24-31S-9W  
4305 feet from S Section Line, 2247 feet from E Section Line  
Lease Name: BERTHOLF Well #: 2-A  
County: HARPER Total Vertical Depth: 3057 feet

Operator License No.: 31191  
Op Name: R & B OIL & GAS, INC.  
Address: 904 N. LOGAN PO BOX 195  
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3055		225 SX
SURF	8.625	221		200 SX

\$ 99.35

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/03/2007 8:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 737-3410

Proposed Plugging Method: PLUG BACK 50 ABOVE THE PERFS AND COP WITH 4 SKS OF CMT. RECOVER PIPE. SPOT 35 SX CMT AT 1500. 35 SX AT 900, CIRC FROM 270'. PERFS 2901-2903. -98.24720,37.33806.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/03/2007 5:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE WELL WOULD NOT BLOW DOWN, PUMPED 30 SKS OF 3% CACL TO 2700' AND LET SET FOR 2 HRS SHUT IN PRESSURE 1700#. RAN WIRELINE, FOUND TOP OF CMT AT 2375' TIED ONTO 4.5 CASING AND PRESSURED TESTED PLUG. PRESSURED TO 1200#. HELD PRESSURE. WENT IN TO RIP CASING. THE CASING WAS RECOVERED FROM 1910' AND PULLED TO 1500', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 900', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 270', WHERE CMT WAS CIRC. TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2901	2903		

**INVOICED**  
DATE 7-2-07  
INV. NO. 2008060014

Remarks: COPELAND ACID AND CMTG. 60/40% 4% GEL

Plugged through: CSG

District: 02

Signed  (TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-2/3

JUN 19 2007

CONSERVATION DIVISION  
WICHITA, KS

PKT