

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19275-00-01
Spot: NWNWSE Sec/Twnshp/Rge: 19-34S-6E
2329 feet from S Section Line, 2380 feet from E Section Line
Lease Name: DUNN Well #: 7
County: COWLEY Total Vertical Depth: 3140 feet

Operator License No.: 32917
Op Name: RICHARDSON AND SON OIL, INC.
Address: 17295 151ST ROAD
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3129		300 SX
SURF	10.75	108		
T1	2.375	2720		

\$102.05

Well Type: EOR UIC Docket No: E16839.3 Date/Time to Plug:
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C
Proposal Rcvd. from: JIM BRADEN Company: BRADEN PETROLEUM WELL PLU Phone: (620) 222-1252

Proposed Plugging Method: INACCORDANCE WITH KCC REGULATIONS.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 04/12/2007 2:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

04-02-2007, SANDED BACK 50' ABOVE PERFS @ 3030', DUMP BAILED 4 SXS CEMENT ON TOP, 04-05-2007, CUT OFF SURFACE HEAD. HAD CEMENT @ 6' AROUND BACKSIDE OF 4-1/2" CASING, SHOT HOLES @ 350', 4-12-2007, RJH W/TBG @ 350' BRADEN PETROLEUM MIXED & PUMPED 32 SXS 60/40 POZMIX 4% GEL TO SURFACE TO P.A. COMPLETE 1400 04-02-2007, CEMENT CIRCULATED TO SURFACE. BRADEN CEMENT TICKET #07-567.

Perfs:

Top	Bot	Thru	Comments
3082	3090		

INVOICED
DATE 7-2-07
INV. NO. 2008060017

Remarks: PERFS 3082'-3090' -096.83667.37.10708

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 19 2007
CONSERVATION DIVISION
WICHITA, KS