

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-30004-00-00

Spot: NWSENNW

Sec/Twnshp/Rge: 25-19S-22W

766 feet from N Section Line, 2086 feet from W Section Line

Lease Name: BORGER A

Well #: 2

County: NESS

Total Vertical Depth: 4410 feet

Operator License No.: 4767

Op Name: RITCHIE EXPLORATION, INC.

Address: BOX 783188 8100 E 22ND ST. N. #700
WICHITA, KS 67278

String Size Depth (ft) Pulled (ft) Comment

PROD 4.5 4409 0 WITH 100 SX CMT

SURF 8.625 507 WITH 300 SX CMT

\$143.33

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/11/2007 11:45 AM

Plug Co. License No.: 99996

Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: BENNIE DILLS

Company: RITCHIE EXPLORATION

Phone: (316) 691-9500

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING REPORT.

Plugging Proposal Received By: MICHAEL MAIER

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 06/11/2007 4:30 PM

KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TUBING TO 4370' & PUMPED 40 SX COMMON CMT WITH 3% CC. PULLED TUBING TO 1500' & PUMPED 60 SX COMMON CMT WITH 3% CC. WAITED 1 1/2 HOURS. TESTED CASING. HELD AT 500#. PEFORATED AT 700'. TIED ONTO CASING AND PUMPED 150 SX CMT. DID NOT CIRCULATE. MAXIMUM PRESSURE 1700#. SHUT IN PRESSURE 800#. TIED ONTO BACKSIDE AND PUMPED 15 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4394	4404		

INVOICED


DATE 7-2-07

INV. NO. 2008060018

Remarks: USED 60/40 POZMIX 6% GEL & COMMON CMT WITH 3% CC BY ALLIED.

Plugged through: TBG

District: 01



Signed

Michael Maier
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 19 2007

CONSERVATION DIVISION
WICHITA, KS