

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-125-30832-00-00

Spot: W2SENE

Sec/Twnshp/Rge: 11-34S-14E

3400 feet from S Section Line,

1000 feet from E Section Line

Lease Name: RBN OWENS LEASE

Well #: 2

County: MONTGOMERY

Total Vertical Depth: 669 feet

Operator License No.: 33297

Op Name: ROCKIN BAR NOTHING RANCH, INC.

Address: 2339 COUNTY RD 2800
INDEPENDENCE, KS 67301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	22		9 SX CMT

\$ 35.00

Well Type: DH

UIC Docket No:

Date/Time to Plug: 10/21/2005 9:00 AM

Plug Co. License No.: 31440

Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC

Proposal Rcvd. from: TONY CARPENTER

Company: CONSOLIDATED OIL WELL SERVI Phone: (620) 431-9210

Proposed Plugging Method: 5-1/8 OPEN HOLE - 50' CONCRETE @ TD GELSPACER, 50' CONCRETE @ 400' GEL SPACER AND CONCRETE FROM 250' TO SURFACE.

Plugging Proposal Received By: ALAN DUNNING

WitnessType: NONE

Date/Time Plugging Completed: 10/21/2005 5:00 PM

KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

A cement string was lowered to 669' and a 50' cement plug pumped thru cement string. A gel spacer was then placed to 400'. A 50' cement plug was placed at 400'. A gel spacer was then placed to 250'. The well was then filled from 250' to surface with cement. A total of 70 sacks of portland cement were used to plug well.

RECEIVED
KCC DISTRICT #3

JUN 14 2007 AMD

CHANUTE, KS

INVOICED
DATE 7-2-07
INV. NO. 200 8060019

Remarks:

Plugged through: OH

District: 03

Signed

Alan M. Dunning
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 20 2007

CONSERVATION DIVISION
WICHITA, KS