

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-00616-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 28-32S-12W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: TEDROW Well #: 1
County: BARBER Total Vertical Depth: 4922 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N. MARKET, SUITE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4365		WITH 2 SX CMT
PROD	5.5	4486	3000	WITH 100 SX CMT \$ 159.97
SURF	8.625	307		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/07/2007 2:15 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4370' WITH 2 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 330' WITH 40 SX CMT. PLUG AT 20' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/07/2007 3:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4365' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LAID DOWN 5 1/2" CASING & RUN 2 3/8" TUBING IN TO SPOT PLUGS THROUGH. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 340' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4420	4430		

INVOICED
DATE 7-2-07
INV. NO. 2008 060030

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 19 2007

CONSERVATION DIVISION
WICHITA, KS