

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-22267-00-00  
Spot: S2SESESE Sec/Twnshp/Rge: 27-29S-4E  
124 feet from S Section Line, 332 feet from E Section Line  
Lease Name: E B SHAWVER Well #: 9-27  
County: BUTLER Total Vertical Depth: 2918 feet

Operator License No.: 6044  
Op Name: STELBAR OIL CORPORATION, INC.  
Address: 1625 N WATERFRONT PARKWAY  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2817		
PROD	5.5	2918		100 SX CMT
SURF	8.625	254		125 SX CMT

*\$ 94.84*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/27/2007 8:00 AM  
Plug Co. License No.: 6044 Plug Co. Name: STELBAR OIL CORPORATION, INC.  
Proposal Rcvd. from: ROBBIE WILLIAMS Company: STELBAR OIL CORP. Phone: (316) 641-0024

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/19/2007 10:00 AM KCC Agent: DUANE KRUEGER

**Actual Plugging Report:**

4-17-2007, SET CIBP @ 2817', DUMP BAILED 5 SXS CEMENT ON TOP, SHOT 5-1/2" CASING @ 841', LAYED DOWN 20 JTS 5-1/2" CSG (841'). 4-19-2007, RIH W/TBG @ 307', ESTABLISHED CIRCULATION, CONSOLIDATED MIXED & PUMPED 105 SXS 60/40 POZMIX 4% GEL TO SURFACE. P.A. COMPLETE 1000 04-19-2007. CEMENT CIRCULATED TO SURFACE. CONSOLIDATED CEMENT TICKET #17043.

**Perfs:**

Top	Bot	Thru	Comments
2838	2860		

**INVOICED**  
DATE 7-2-07  
INV. NO. 2008060023

Remarks: -096.97272,37.49056, PERFS 2838-2860'

Plugged through: TBG

District: 02

Signed *Duane Krueger*  
(TECHNICIAN)

RECEIVED Form CP-2/3  
KANSAS CORPORATION COMMISSION

JUN 19 2007

CONSERVATION DIVISION  
WICHITA, KS

*PKT*

*a*