

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-01998-00-00  
Spot: NWNWNW Sec/Twnshp/Rge: 1-10S-20W  
4950 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: WILSON B Well #: 6  
County: ROOKS Total Vertical Depth: 3786 feet

Operator License No.: 32500  
Op Name: T & P OIL & GAS, L.L.C.

Address: 7801 METCALF  
OVERLAND PARK, KS 66204

| String | Size  | Depth (ft) | Pulled (ft) | Comment           |
|--------|-------|------------|-------------|-------------------|
| PROD   | 5.5   | 3779       | 0           | w/unknown sxs cmt |
| SURF   | 8.625 | 210        | 0           | w/unknown sxs cmt |

\$123.05

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/18/2007 10:00 AM  
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC  
Proposal Rcvd. from: IRVIN HASELHORST Company: T&P OIL & GAS, LLC Phone: (785) 623-1154

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 1/4# flocele per sack - 500# hulls.  
Emergency plug with rig over the hole.  
Squeezed at 1156' w/110 sxs on March 1954; squeezed at 801'-972' w/200 sxs on July 1989.  
Packer sanded off in hole.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/18/2007 4:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech RIH and shot tubing off at 2867'.  
Pulled tubing to 2800'. Rigged to tubing - pumped 50 sxs cement with 200# hulls mixed in.  
Pulled tubing to 2450'. Rigged to tubing - pumped 100 sxs 60/40 pozmix with 100# hulls mixed in.  
Pulled tubing to 1750'. Rigged to tubing - pumped 140 sxs cement with 200# hulls mixed in.  
Pulled tubing. Rigged to 5 1/2" casing with a swedge - pumped 15 sxs cement.  
Max. P.S.I. 600#. S.I.P. 500#.  
Rigged to 8 5/8" casing - pumped 5 sxs cement - blew small hole in top of pipe.

Perfs:

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUN 20 2007  
CONSERVATION DIVISION  
WICHITA, KS

INVOICED  
DATE 7-2-07  
INV. NO. 2008060024

Remarks: ALLIED CEMENTING COMPANY-TICKET #21996.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

Form CP-2/3

JUN 19 2007

FRANCIS OIL & GAS COMPANY #6

WILSON 'B'

1-10-20W 22  
NW NW NW

Contr. WOODY SPEER

ROOKS

County

E 2253

Comm.

Comp. 1-9-53

IP


3000 BOPD

DRAW DOWN

| Tops | Depth | Datum |
|------|-------|-------|
| HEEB | 3451  | -1198 |
| KC   | 3494  | -1241 |
|      |       |       |
| CONG | 3734  | -1481 |
|      |       |       |
| ARB  | 3780  | -1527 |
|      |       |       |
| T.D. | 3786  | -1533 |

Casing  
 8" 210 CO 3780  
 5" 3779 40 BOPH

MARCOTTE



INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS