

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Ritchie Exploration, Inc.

Address: P. O. Box 783188

Phone: (316) 691-9500 Operator License #: 4767

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 06/11/2007 (Date)

by: Mike Maier (KCC District Agent's Name)

Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No

Producing Formation(s): List All (If needed attach another sheet)

Mississippian Depth to Top: 4394' Bottom: 4404' T.D. 4410'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 135-30004 -00-00

Lease Name: Borger A-P KCC PKT 7/11/07 per

Well Number: #2 oper John N.

Spot Location (QQQQ): nw se - NE - NW CP2/3
766 Feet from ☒ North / ☐ South Section Line

2086 Feet from ☐ East / ☒ West Section Line

Sec. 25 Twp. 19 S. R. 22 ☐ East ☒ West

County: Ness

Date Well Completed: 12/30/1964

Plugging Commenced: 06/11/2007

Plugging Completed: 06/11/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Mississippian	Oil & Water	4394'	4404'	8.625"	507'	-0-
				4.50"	4409'	-0-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 2 3/8" tubing to 4370'. Pumped 40 sx Common cement + 6% CC down tubing. Pulled tubing up to 1520'. Pumped 60sx Common cement + 3% CC down tubing. Pulled tubing out of hole. Perforate at 700' & 701', hooked onto casing. Pumped 160 sx 60/40 Pozmix cement + 6% gel + 100# hulls down 4 1/2" casing to 1700#, shut in at 800#. Loaded 8 5/8 casing with 15 sx 60/40 Pozmix cement + 6% gel to 500#, shut in. Plugging complete at 4:30 PM on 06/11/2007, witnessed and approved by Mike Maier w/ the KCC.

Name of Plugging Contractor: Allied Cementing License #: 99996 PKT

Address: P. O. Box 31 Russell, KS 67665

Name of Party Responsible for Plugging Fees: Ritchie Exploration, Inc.

State of Kansas County, Ness, ss.

John Niernberger - employee of Ritchie Exploration, Inc. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) John Niernberger

(Address) P. O. Box 783188 Wichita, KS 67278-3188



and SWORN TO before me this 3rd day of July, 20 07

Joyce Cochran
Notary Public

My Commission Expires: 4-10-11

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 05 2007

CONSERVATION DIVISION

ALLIED CEMENTING CO., INC. 24229

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Great Bend
Kansas

DATE <u>6-11-07</u>	SEC.	TWP.	RANGE	CALLED OUT <u>7:30 AM</u>	ON LOCATION <u>10:30 AM</u>	JOB START <u>3:30 PM</u>	JOB FINISH <u>4:30 PM</u>
LEASE <u>Borger A</u>	WELL # <u>D-2</u>	LOCATION <u>Borger 6.5 1/2 W 3/4 N</u>			COUNTY <u>Deer</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one)							

CONTRACTOR H-D Well Service
TYPE OF JOB Old Hole
HOLE SIZE _____ T.D. _____
CASING SIZE 4 1/2 DEPTH _____
TUBING SIZE 2" DEPTH 4370
DRILL PIPE _____ DEPTH _____
TOOL _____ DEPTH _____
PRES. MAX 1800 MINIMUM _____
MEAS. LINE _____ SHOE JOINT _____
CEMENT LEFT IN CSG. _____
PERFS. _____
DISPLACEMENT _____

OWNER Ritchie Exploration
CEMENT
AMOUNT ORDERED 100s x Conn 3% cc
280 60/40 6 1/2" dia
100 # Halls (USED 175 # 60/40 #)
COMMON 205 # @ 11.10 2275.50
POZMIX 70 # @ 6.20 434.00
GEL 9 # @ 16.65 149.85
CHLORIDE 3 # @ 46.60 139.80
ASC _____ @ _____
Halls 100 # @ 25.50 25.50

EQUIPMENT
PUMP TRUCK CEMENTER A. Weighman
224 HELPER Randy
BULK TRUCK
344 DRIVER Don
BULK TRUCK
_____ DRIVER _____

HANDLING 398 # @ 1.90 756.20
MILEAGE 398 # @ 09 18 644.76
TOTAL 4475.6

REMARKS:

4370' mix 40s x Conn. deep 2" tubing
1500' mix 60s x Conn. deep 2" tubing
mix 160s x Conn. 4 1/2" cas. deep 2.88
shut in 800'
mix 15 x Back scale. Shut in 400'
mix 100 # Halls in last 30 x Conn
down 4 1/2 cas. Thanks

SERVICE

DEPTH OF JOB 4370
PUMP TRUCK CHARGE _____ 955.00
EXTRA FOOTAGE _____ @ _____
MILEAGE 18 @ 6.00 108.00
MANIFOLD _____ @ _____
_____ @ _____
_____ @ _____

TOTAL 1063.00

CHARGE TO: Ritchie Explor
STREET _____
CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 05 2007

CONSERVATION DIVISION
WICHITA, KS

TAX _____
TOTAL CHARGE _____
DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Don R. Weighman
Allied Cementing Co. LLC

PRINTED NAME
Don R. Weighman