

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-20118-00-00
Spot: NENW Sec/Twnshp/Rge: 4-1S-26W
4620 feet from S Section Line, 3300 feet from E Section Line
Lease Name: SUMNER A Well #: 1
County: DECATUR Total Vertical Depth: 3645 feet

Operator License No.: 3273
Op Name: LOEB, HERMAN L.
Address: PO BOX 524
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3553	0	w/125 sxs cmt
SURF	7.625	257	0	w/125 sxs cmt

118.46

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/12/2007 1:00 PM
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC
Proposal Rcvd. from: ROLAND NYP Company: RGN Phone: (785) 623-8120

Proposed Plugging Method: Ordered out 170 sxs 60/40 pozmix - 10% gel - 300# hulls.
Plug thru tubing.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/12/2007 3:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 1200' & 2010'.
Ran tubing to 2300' - pumped 120 sxs 60/40 pozmix - 10% gel with 200# hulls - cement circulated to surface.
Max. P.S.I. 750#. S.I.P. 650#.
Pulled all tubing -open hole - pumped 50 sxs 60/40 pozmix - 10% gel to top off casing.
Pumped 7 5/8" x 4 1/2" annulus. Max. P.S.I. 600#.

Perfs:

INVOICED
DATE 7-10-07
INV. NO. 2008060071

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 25 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Pat Bedore PART I

(TECHNICIAN)

JUN 15 2007

PKT

ABERCROMBIE DRILLING, INC.
WICHITA, KS.

#1 SUMNER

4-1-26W
C NE NW

Contr. CO. TOOLS

Cty. DECATUR

Geol. JACK K. WHARTON

Pool BLEES EXT.

E. 2547 KB Cm. 9/8/69 Cp. 11/6/69 IP PMP 100 BOPD, 7%

API 15-039-20, 118

WTR GR 33.4/
LANS 3436-41

LOG Tops

Depth

Datum

ANH 2012 + 535
HEEB 3282 - 735
LANS 3324 - 777
BKC 3533 - 986
GRAN W 3616 - 1069
LTD 3640 - 1093

Csg. 7" 257/125 SX; 5 1/2" 3553/125
DV TOOL 2025
DST 3294-3340/105", 5' FO 45'
OCM, 126' OCMW, BHP 1105-
1003#/30", FP 39-42#, FP 47-
102#
DST 3336-3380/120", 2' OIL, 3'
MCO, 120' MC OILY WTR, BHP
1079-1063#/30", FP 31-46#,
FP 69-85#
DST 3422-3460/75", 93' SOCM,
63' OCM, 252' MO, 315' HMCO,
BHP 1065-964#/30", FP 86-
141#, FP 172-323#
DST 3455-3515/90", 78' OCM, BHP
745-251#/30", FP 28-29#, FP
39-47#

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

(OVER)