

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-21428-00-00  
Spot: NENWSW Sec/Twnshp/Rge: 20-7S-17W  
2310 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: KRILEY B Well #: 3  
County: ROOKS Total Vertical Depth: 3266 feet

Operator License No.: 5663  
Op Name: HESS OIL COMPANY  
Address: PO BOX 1009  
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3076		
L1	4.5	3284		
PROD	5.5	3260	0	150 SX \$ 106.15
SURF	8.625	1280	0	450 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/13/2007 1:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: HESS OIL COMPANY Phone: (620) 562-8088

Proposed Plugging Method: Ordered 175 sxs 60/40 pozmix - 10% gel - 200# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/13/2007 4:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Tubing at 2800' - spotted 35 sxs 60/40 pozmix - 10% gel w/100# hulls.  
Ran tubing to 1280' - pumped 90 sxs 60/40 pozmix - 10% gel w/200# hulls - cement circulated to surface.  
Max. P.S.I. 300#.  
Pulled all tubing. Open hole filled with 10 sxs 60/40 pozmix - 10% gel  
Backside pressured to 500# immediately.

Perfs:

Top	Bot	Thru	Comments
2958	2962		

**INVOICED**  
DATE 7-10-07  
INV. NO. 2008060065

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUN 27 2007

Remarks: COPELAND ACID & CEMENTING COMPANY-TICKET #031765.

CONSERVATION DIVISION  
WICHITA, KS

Plugged through: TBG

District: 04

Signed Pat Bedore 6-25-07  
(TECHNICIAN)


JUN 21 2007

PAT

COLUMBIA PETROLEUM, INC. REPLACEMENT CARD  
PARKADE PLAZA, #8 #3 "B" KRILEY 20-7-17W  
COLUMBIA, MO 65201 NE NW SW

CONTR RANGER DRILLING CO. CTY ROOKS  
GEOL ERIC WADDELL FIELD RIFFE

ELV 1772 KB SPD 12/2/81 CARD ISSUED 4/15/82 # D&A/ARB  
1767 GL  
API 15-163-21,428



SMP	Tops	Depth/Datum
BKC		3189-1417
NO OTHER TOPS AVAILABLE		
RTD		3266-1494
	Amh	+ 614

8 5/8 " 1280; 5 1/2 " 3260  
MICT - CO. (ARB OH), SWB DWN, GSO, NAT, POP, PROD NON-COMMERCIAL, (SINK HOLE), P&A

INFO RELEASED: 12/1/83 - WAS D&A - TIGHT HOLE

COPYRIGHT 1983  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS