

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21568-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 20-7S-17W
2970 feet from S Section Line, 2310 feet from E Section Line
Lease Name: ELDON KRILEY F Well #: 3
County: ROOKS Total Vertical Depth: 3296 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3289	0	150 SX
SURF	8.625	1144	0	425 SX

\$ 107.12

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/20/2007 1:00 PM
Plug Co. License No.: 5663 Plug Co. Name: HESS OIL COMPANY
Proposal Rcvd. from: ARNIE HESS Company: HESS OIL COMPANY Phone: (785) 731-5165

Proposed Plugging Method: Ordered 175 sxs 60/40 pozmix - 10% gel - 200# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/20/2007 3:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2800' - spotted 35 sxs 60/40 pozmix - 10% gel w/100# hulls.
Max. P.S.I. 800#. S.I.P. 900#.
Pulled tubing to 1240' - pumped 145 sxs 60/40 pozmix - 10% gel w/100# hulls.
Max. P.S.I. 500#. Had circulation of cement to surface.
Pulled all tubing - open hole - filled casing with 15 sxs 60/40 pozmix - 10% gel to surface.

Perfs:

Top	Bot	Thru	Comments
3290	3296		

INVOICED

DATE 7-10-07
INV. NO. 2008060065

Remarks: COPELAND ACID AND CEMENTING.

Plugged through: TBG

District: 04

Signed Pat Bedore 6-25-07
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

JUN 27 2007

CONSERVATION DIVISION
WICHITA, KS

JUN 25 2007

Handwritten initials

