

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21669-00-00
Spot: NWSENW Sec/Twnshp/Rge: 20-7S-17W
3630 feet from S Section Line, 3630 feet from E Section Line
Lease Name: KRILEY F Well #: 4
County: ROOKS Total Vertical Depth: 3257 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3256	0	150/175 SX
SURF	8.625	1127	0	450 SX

\$ 105.85

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/19/2007 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: HESS OIL COMPANY Phone: (620) 562-8088

Proposed Plugging Method: Ordered 175 sxs 60/40 pozmix - 10% gel - 200# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/19/2007 5:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Tubing at 2800' - spotted 35 sxs 60/40 pozmix - 10% gel w/100# hulls.
Max. P.S.I. 150#.
Pulled tubing to 1240' - pumped 110 sxs 60/40 pozmix - 10% gel w/100# hulls - cement circulated.
Max. P.S.I. 700#.
Pulled all tubing - pumped 20 sxs 60/40 pozmix - 10% gel. Open hole to fill casing to surface.
Tied onto backside - pressured to 400# immediately.

Perfs:

Top	Bot	Thru	Comments
3256	3260		

INVOICED

DATE 7-10-07
INV. NO. 2008060065

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #C32075.

Plugged through: TBG

District: 04

Handwritten initials

Signed Pat Bedore 6-25-07
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

JUN 27 2007

CONSERVATION DIVISION
WICHITA, KS

JUN 21 2007

Handwritten initials PKT

COLUMBIA PETROLEUM, INC. #4 "F" KRILEY 20-7-17W
 PARKADE PLAZA, #8 NW SE NW
 COLUMBIA, MO 65201
 CONTR LAWBANCO DR LG. CTY ROOKS
 GEOL ERIC WADDELL FIELD RIFFE
 E 1750 KB CM 4/21/82 CARD ISSUED 8/26/82 IP P 50 BOPD & 10% W
 ARB OH 3256-57

+	+
+	+

API 15-163-21,669

LOG TOPS	DEPTH	DATUM
TOP	2678	- 928
HEEB	2888	-1138
TOR	2911	-1161
LANS	2931	-1181
BKC	3166	-1406
PENN-CGL	3200	-1450
SIMP	3233	-1483
ARB	3255	-1505
RTD	3257	-1507

B 5/8" 1127/450sx; 5 1/2" 3256/150sx
 NO DSTS
 MICT - CO, (ARB OH) SWB DWN W/GSO,
 POP, P 120 BOPD, TR W, INITIALLY,
 STATE REG AT 50 BOPD & 10% W, 5/8/82

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS