

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-039-20084-00-00  
Spot: NESWSWSW Sec/Twnshp/Rge: 4-1S-26W  
633 feet from S Section Line, 4900 feet from E Section Line  
Lease Name: SUMNER B Well #: 1  
County: DECATUR Total Vertical Depth: 3595 feet

Operator License No.: 3273  
Op Name: LOEB, HERMAN L.  
Address: PO BOX 524  
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3595	0	w/125 sxs cmt
SURF	8.625	258	0	w/200 sxs cmt

\$ 116.84

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/18/2007 9:00 AM  
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC  
Proposal Rcvd. from: ROLAND NYP Company: RGN Phone: (785) 623-8120

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 10% gel - 400# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/18/2007 12:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 1980' - spotted 50 sxs 60/40 pozmix - 10% gel w/200# hulls - had circulation of cement.  
Pulled tubing to 1400' - pumped 60 sxs 60/40 pozmix - 10% gel w/200# hulls - had circulation of cement.  
Max. P.S.I. 650# - 750#.  
Pulled all tubing. - pumped 65 sxs 60/40 pozmix - 10% gel down backside.  
Max. P.S.I. 100#.  
Open hole - 25 sxs 60/40 pozmix - 10% gel to fill casing to surface.

Perfs:

Remarks: WELL PERMITTED AS SUMNER #A-1. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Pat Bedore 6-25-07  
(TECHNICIAN)

INVOICED  
DATE 7-10-07  
INV. NO. 2008060071

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-2/3

JUN 27 2007

CONSERVATION DIVISION  
WICHITA, KS

JUN 21 2007

*[Handwritten initials]*

