

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21803-00-00
Spot: NWSESWNW Sec/Twnshp/Rge: 18-33S-43W
2135 feet from N Section Line, 880 feet from W Section Line
Lease Name: BOOKSTORE B Well #: 1
County: MORTON Total Vertical Depth: 5084 feet

Operator License No.: 5447

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1432		WITH 500 SX CMT

Op Name: OXY USA, INC.

Address: 5 E. GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

165.23

Well Type: DH

UIC Docket No:

Date/Time to Plug: 05/21/2007 12:00 AM

Plug Co. License No.: 30606

Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: WES WILLIMON

Company: OXY USA

Phone: (713) 215-7000

Proposed Plugging Method: 1ST PLUG AT 1460' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: NONE

Date/Time Plugging Completed: 05/21/2007 2:00 AM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

1ST PLUG AT 1460' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

INVOICED


DATE 7-10-07

INV. NO. 2008060078

Remarks: USED 60/40 POZMIX 6% GEL BY JET STAR.

Plugged through: DP

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

JUL 02 2007

CONSERVATION DIVISION