

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-14402-00-00
Spot: NENENW Sec/Twnshp/Rge: 9-20S-11W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease Name: HERTER Well #: 1
County: BARTON Total Vertical Depth: 3311 feet

Operator License No.: 30364
Op Name: RESOURCE OPERATIONS, INC.
Address: BOX 9487
TULSA, OK 74157

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3304	0	w/unknown sxs cmt
SURF	8.625	150	0	w/unknown sxs cmt

107.61

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/20/2007 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: Ordered 285 sxs 60/40 pozmix - 10% gel with 1/4# flocele per sack - 500# hulls.
Emergency plug with rig over the hole.
Log Tech perfed at 1050' - 490' - 200'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/20/2007 6:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

RIH with tubing to 2015'. Rigged to tubing - pumped 100 sxs 60/40 pozmix with 300# hulls mixed in.
Pulled tubing to 1250'. Rigged to tubing - pumped 140 sxs with 200# hulls mixed into circulate cement out of 5 1/2" casing.
Pulled tubing - rigged to 5 1/2" casing with a swedge - pumped 30 sxs cement to circulate cement out of 8 5/8" casing.
Shut in 8 5/8" - pumped 15 sxs on 5 1/2" casing.
Max. P.S.I. 300#. S.I.P. 250#.

INVOICED
DATE 7-10-07
INV. NO. 200 8060084

Remarks: ALLIED CEMENTING COMPANY-TICKET #30564.

Plugged through: TBG

District: 04

Signed _____
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

JUN 25 2007

CONSERVATION DIVISION
WICHITA, KS

JUN 21 2007

PPT

PHIL HAN OIL COMPANY

#1

HERTER

9-20-11W /
NE NE NW

Contr.

BARTON

County

E. 1770

Comm. 7-1-48

Comp. 8-27-48

IP 50 BOPD

Tops	Depth	Datum
ANH	480	+1290
LANS	3050	-1280
ARB	3304	-1534
T.D.	3311	-1541

Casing

8" 150 ACID 3000
5" 3304 PMP 6 BOPH/24 HRS

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

+	+	+
+	+	+
+	+	+