

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-21348-00-002
Spot: SESESE Sec/Twnshp/Rge: 14-20S-16W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: DIRKS Well #: 2-A
County: PAWNEE Total Vertical Depth: 4000 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 SOUTH MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3999	2500	WITH 222 SX CMT
SURF	8.625	1084		WITH 400 SX CMT

130.00

Well Type: OIL UIC Docket No: D26230.0 Date/Time to Plug: 06/13/2007 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND TO 3675' & 5 SX CMT. PLUG AT 1130' WITH 15 SX GEL & 50 SX CMT. PLUG AT 400' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/13/2007 10:30 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3675' & 5 SX CMT WITH BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1130' WITH 15 SX GEL - 50 SX CMT. 2ND PLUG AT 400' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3786	3790		

INVOICED
DATE 7-10-07
INV. NO. 2008060087

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

JUL 02 2007

CONSERVATION DIVISION
WICHITA, KS

[Handwritten initials]