

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-01262-00-00
Spot: NESESW Sec/Twnshp/Rge: 24-20S-16W
990 feet from S Section Line, 2310 feet from W Section Line
Lease Name: BIXBY P Well #: 2
County: PAWNEE Total Vertical Depth: 3805 feet

Operator License No.: 30737
Op Name: YOST, M.A. OPERATIONS, INC
Address: 611 S FOSSILL PO BOX 811
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3799	2040	
SURF	8.625	1082		

123.66

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/08/2007 2:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SANDED TO 3717' & 5 SX CMT. PLUG AT 1130' WITH 15 SX GEL & 50 SX CMT. PLUG AT 400' WITH 40 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/08/2007 4:25 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3717' & 5 SX CMT WITH BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1130' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 400' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.


Perfs:

INVOICED
DATE 7-10-07
INV. NO. 2008060090

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed

Richard M. Lacey

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CF 2/3

JUL 02 2007

CONSERVATION DIVISION
WICHITA, KS

[Handwritten initials]