

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-163-21-465 -00-00

LEASE NAME Bice

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER No. 1

1650 Ft. from S Section Line

1650 SE-SE-NW  
Ft. from E Section Line

SEC. 16 TWP. 10 RGE. 17 (E) or (W)

COUNTY Rooks

LEASE OPERATOR Amerkan Resources Group Limited

ADDRESS 205 E. Central Suite 120

PHONE#(316) 267-8416 OPERATORS LICENSE NO. 5286

Character of Well Oil

Date Well Completed 8-16-82

Plugging Commenced 6-1-87

(Oil, Gas, Dry, SWD, Input, Water Supply, Well)

Plugging Completed 6-1-87

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Hays Office

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Ks. City Cong Depth to Top 3355 Bottom 3664 T.D. 3698

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Dakota	Water	1250	800	4 1/2"	Perf & Squeezed w/	120sx
LKC	Oil/water	3586	3335	4 1/2"	Cmt w/	200sx
Conglomerate	Oil/water	3660	3616	4 1/2"	Cmt w/	200sx
Arbuckle	Water	TD	3659	4 1/2"	Cmt w/	200sx 30sx Cmt w/ 3sx Hulls

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pumped in 4 1/2" Casing. 30sx Cmt. w/ 3sx Hulls, (15bbl slurry) followed w/ 15 bbls fluid, released wiper plug, ran WLM to 1285'. Perf csg @ 1250' (2holes); 800' (2holes); and 260' (4holes). Pumped in 4 1/2" csg 120sx cmt (60 bbl slurry) w/ 1 sx hulls per 5 bbls. Cmt circ. Annulus @ 30bbls out, shut in same. Pressured up to 700# shut in @ 400#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_

Address Russell, Kansas

STATE OF Kansas COUNTY OF SEDGWICK, ss.


F. Calvin Jones (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 205 E. Central Su. 120 Wichita, KS.

67202

8th day of June, 19 87



AND SWORN TO before me this \_\_\_\_\_ day of \_\_\_\_\_, 1987

STATE CORPORATION COMMISSION  
Sally R. Byers  
Sally R. Byers, Notary Public

My Commission Expires: December 6, 1988

RECEIVED  
06-09-1987  
CONSERVATION DIVISION  
Wichita, Kansas