

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Rooks SEC. 10 TWP. 10 RGE. 17 E/W
Location as in quarters or footage from lines:

NW SE NW

Lease Owner Horizon Petroleum Corp.
Lease Name Conway Well No. 1
Office Address 833 North Waco Wichita, KS 67203
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed 12-19-83
Application for plugging filed 12-19-83
Plugging commenced _____ 12-19-83
Plugging completed _____ 12-19-83
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3570'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____
feet to _____ feet for each plug set.

Bottom Plug: @3520' w/20 sacks 50/50 pozmix 4% gel 3% cc thru drill pipe
Next Plug: @ 1325' w/20 sacks " " " " " " "
Next Plug: @ 650' w/80 sacks & 1 sack cello flake " " " "
Next Plug: @ 250' w/40 sacks " " " " " "
Top Plug: @ 40' w/solid bridge of 1/2 sack hulls & 10 sacks cement
10 sacks in Rat Hole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.
Bill Draney (employee of owner) or (~~owner or operator~~) of the

above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Bill Draney
Box 823 Great Bend, KS 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 23 day of December, 1983

Dorothy M. Hague
Notary Public.

My Commission expires: 4-29-86

RECEIVED
STATE CORPORATION COMMISSION

DEC 23 1983
12-23-1983
CONSERVATION DIVISION
Wichita, Kansas

15-163-22205-00-00

DRILLER'S WELL LOG

DATE COMPLETED: December 12, 1983
DATE COMPLETED: December 19, 1983

Horizon Petroleum
CONWAY #1
NW SE 1/4
Sec. 10, T10S, R17W
Rooks County, Ks.

ELEVATION: 2071 K.B.

0 - 1324' Surface Soil, Post Rock, Shale
1324 - 1360' Anhydrite
1360 - 2958' Lime & Shale
2958 - 3190' Lime
3190 - 3194' Shale
3194 - 3211' Lime & Shale
3211 - 3502' Lime
3502 - 3570' Dolomite
3570' RTD

FORMATION DATA

Anhydrite 1324'
Topeka 1360'
Heebner 3190'
Toronto 3211'
Lansing K.C. 3233'
Ari buckle 3502'
RTD 3570'

Surface Pipe: Set new 8-5/8"
20# pipe @216' w/140 sacks
60/40 pozmix 2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARFORD

Bill Draney of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Bill Draney

Subscribed and sworn to before me this 23 day of December 1983.

My Comm. Expires:

4-29-86

Deborah M Hague
Notary Public

REC-11
STATE CORPORATION COMMISSION
DEC 23 1983
OBSERVATION
Wichita, Kansas