

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05799-00-01
Spot: S2SWNW Sec/Twnshp/Rge: 21-11S-17W
2970 feet from S Section Line, 4620 feet from E Section Line
Lease Name: HADLEY Well #: 2
County: ELLIS Total Vertical Depth: 3410 feet

Operator License No.: 33729
Op Name: STP PETROLEUM DEVELOPMENT, LP
Address: PO BOX 2230
KELLER, TX 76244

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|------|------------|-------------|-------------------|
| PROD | 7 | 3408 | 0 | w/unknown sxs cmt |
| SURF | 12 | 85 | 0 | w/unknown sxs cmt |

\$ 110.83

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/10/2007 9:00 AM
Plug Co. License No.: 6819 Plug Co. Name: SCOTT'S WELL SERVICE INC
Proposal Rcvd. from: LEO DORZWEILER Company: STP PETROLEUM DEVELOPMENT Phone: (817) 431-6336

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 600# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/10/2007 1:10 PM KCC Agent: PAT STAAB

Actual Plugging Report:

STP entered hole - got to 2100'.
Re-entered - got to 1200'. Casing broke in on OWWO.
Scott's Well Service ran in hole with tubing to 1100'.
Quality Well Service rigged to tubing - pumped 50 sxs neat followed with 50 sxs cement with 100# hulls mixed in.
Pulled tubing to 790'. Quality rigged to tubing - pumped 150 sxs 60/40 pozmix.
Pulled tubing to 312' - Quality rigged to tubing - pumped 50 sxs to circulate cement to surface.
Pulled tubing - topped off 12" and 7" casing with 5 sxs 60/40 pozmix.
Hole standing full.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3408 | 3410 | OH | |

INVOICED
DATE 7-16-07
INV. NO. 2008060117

Remarks: QUALITY WELL SERVICE-TICKET #1554.

Plugged through: TBG

District: 04

PD

Signed _____

James [Signature]
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

JUL 12 2007

CONSERVATION DIVISION
WICHITA, KS

JUL 11 2007

pat

WINKLER & KOCH ENGR CO

#2 HADLEY

21-11-17W

CSL SW NW

Contr.

ELLIS

County

E 1887

Comm. 6-6-40


Comp. 6-23-40

IP

2261 BOPD

| Tops | Depth | Datum |
|------|-------|-------|
| ANH | 1082 | |
| TOP | 2845 | |
| LANS | 3100 | |
| B/KC | 3365 | |
| CONG | 3380 | |
| SIMP | 3390 | |
| ARB | 3408 | |
| TD | 3410 | |

Casing
12" 85
7" 3408
3000' OIH: A/2000



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS