

10-27 4-060596

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-21,937-00-60

NE NW NW /4 SEC. 16, 10 S, 17 W
4950 feet from S section line
4290 feet from E section line

Operator license# 3372 Lease Bice well # 3

Operator: Dixon-Dearmore Oil Co., Inc. County Rooks

Address: 105 S. Broadway Well total depth 3670 feet
Suite 900 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 250 feet

119.27

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Co Tools License#

Address:

Company to plug at: Hour: 10:00A.M Day: 19 Month: October Year: 94

Plugging proposal received from: Mike Dixon

Company: Dixon-Dearmore Oil Co., Inc. Phone: 316-264-9632

Were: Order 275 sxs. 60/40 posmix - 10% gel and hulls.
W.L. to 3583'. Perfs. from 3254' - 3505'.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 11:00A.M, Day: 19, Month: October, Year: 94

Actual plugging report: 8 5/8" to 250' w/150 sxs. 4 1/2" to 3669'
w/150 sxs. Perforated at 825' - 1360' - 1875'. Tied onto production
casing and pumped 200 sxs. cement with 400# hulls scattered throughout.
Tied onto annulus with instant 500# S.I.P. Tied back onto production
casing and pumped additional 65 sxs. of cement. Max. 300# P.S.I.
S.I.P. 150#.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC X, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING X. Elevation: 2076 GL

I did [X] did not [] observe the plugging.

INVOICED

DATE 11-2-94

INV. NO. 41557

Herb Deines (agent) 10-27-1994