

6 040759

JUN 0 1 1987

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 163-21,465-00-00

SE SE NW, SEC. 16, T 10 S, R 17 W/E

_____ feet from S section line

_____ feet from E section line

Lease Name Bice Well # 1

County _____ Rooks 120.25

Well Total Depth 3700 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 251' w/160

TECHNICIAN'S PLUGGING REPORT

Operator License # 5286

Operator: Amerkan Res. Group Ltd.

Name & Address 205 East Central

Suite 120

Wichita, Kansas 67202

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Co. License Number _____

Address Russell, KS

Company to plug at: Hour: 9:00 AM Day: 1 Month: June Year: 19 87

Plugging proposal received from Calvin Jones

(company name) Amerkan Res. (phone) _____

were: 4 1/2" Csg set at 3698' w/200 sks cmt.

Perf. 3355 - 3664'. Fluid level at 200', hole in csg at 975'.

Ordered 150 sks. 65/35 Poz, 10% Gel, 2% Lite, w/1/2# per sk of Flo-cele and

12 sks Hulls.

Plugging Proposal Received by Dennis Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:15 Day: 1 Month: June Year: 19 87

ACTUAL PLUGGING REPORT Pumped in 4 1/2" Csg. 30 sks cmt. w/3 sks Hulls, (15 bbls. slurry) followed w/15 bbls fluid, released wiper plug, ran WLM to 1285',

perf csg. at 1250' (2 holes) 800' (2 holes), and 260' 4 holes; Pumped in 4 1/2" csg. 120 sks.

cmt (60 bbls slurry) w/1 sk Hulls per 5 bbls; cmt circ. annulus at 30 bbls out, shut in

same. Pressured up to 700" shut in at 400#.

RECEIVED STATE CORPORATION COMMISSION

Remarks: _____

(if additional description is necessary, use BACK of this information)

INVOICED observe this plugging.

DATE 6-5-87

INV. NO. 17169

Signed Dennis Hamel (TECHNICIAN)

Dennis Hamel