

6010361

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-163-22703-00-00

SW, SEC. 11, T. 10 S., R. 17 W.

990 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9449

Lease Name Darland Well # 1

Operator: Great Eastern Energy

County Rooks 115.38

Name & Address 5660 S. 54th Cir.

Well Total Depth 3550 feet

Englewood Colo.

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 254

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well (D&A)

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Stoepelwerth Drly. License Number \_\_\_\_\_

Address McCook Neb.

Company to plug at: Hour: PM Day: 19 Month: 6 Year: 19 85

Plugging proposal received from Dave Pascal

(company name) Stoepelwerth (phone) \_\_\_\_\_

were: order 210 sx. 50/50 permix 670 gal. 370 c.c.

Heavy mud between plugs.

Pump c.m. down drill pipe.

Elev. 2012 Anhydrite 2255-86 Arbuckle 3489

Dakota 1575 Plugging Proposal Received by Dale F. Balthazor

437 = 740

checked plug, (TECHNICIAN)

Plugging Operations attended by Agent Part

Operations Completed: Hour: 8:45 Day: 19 Month: 6 Year: 19 85

ACTUAL PLUGGING REPORT circ. @ 3480 for 30 mi.

25 sx @ 3480

25 sx @ 1270

100 sx @ 740 with 1 sx Flowline

40 sx @ 280

10 sx @ 40 on Solid Bridge

Remarks: 10 sx in Red Hole can be Allied.

(If additional description is necessary, use BACK of this form.)

INDEXED

DATE 7-10-85

INV. NO. 8808

observe this plugging. Check Plug

Signed Dale F. Balthazor (TECHNICIAN)

27  
6-28-85  
mmf

RECEIVED  
STATE CORPORATION COMMISSION

JUL 01 1985  
07-01-1985  
CONSERVATION DIVISION  
Wichita, Kansas