

6 040357

API NUMBER 15-1163-00089-00-02 ^{KCC}

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW/NE/SE/ SW SEC. 11, T. 10 S, R. 17 ^W

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568 ^{KCC} ap, Lease Name Darland Well # 1

Operator: Kaiser-Franis Le Ben Oil Co County: Rooks 114.05

Name & Address: P.O. Box 791 Well Total Depth 3509 feet

Hays, Kansas Conductor Pipe: Size feet

67601 Surface Casing: Size 8 5/8 feet 141 w/circ.

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Hallikuster Cmty License Number

Address Hays, KS

Company to plug at: Hour: 10:30 AM Day: 19 Month: 3 Year: 19 85

Plugging proposal received from Ray Goutan

(company name) Kaiser-Franis (phone)

were: 5 1/2" csg set @ 3484 - Perfs @ 3148 to 3414

Holds in csg @ 1150'-90' Fish in hole - 7 jts tbg (204') at bottom. Will run tbg.

Ordered 250 sy 6 3/4 pgs 10% gel, 80 sy gel, + 8 sy hulls

Plugging Proposal Received by Dennis J. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:15 PM Day: 19 Month: 3 Year: 19 85

ACTUAL PLUGGING REPORT Ran tbg 3280' -> 1 sy hulls -> 50 sy cmt w/ hull

-> pulled tbg to 2710', pmpd 10 sy gel w/ hulls -> pulled tbg

to 1730' circ cmt to surf w/ 145 sy cmt -> pulled

tbg - pumped in 5 sy cmt pressure up: Hooked up

8 5/8 S. P. pmpd in 10 sy gel w/ 2 hulls -> 55 sy cmt

MAX 300 # P.S.I Shut-in 100 # P.S.I

Remarks: (If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION

INVOICED

DATE 5-14-85

INV. NO. 8124

Signed Dennis J. Hamel
(TECHNICIAN)

MAY 10 1985
05-10-1985
CONSERVATION DIVISION
WICHITA, KANSAS

MAY 15 1985