

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22346-00-01
Spot: SE Sec/Twnshp/Rge: 31-34S-36W
1186 feet from S Section Line, 1198 feet from E Section Line
Lease Name: WINTERS Well #: 3-31
County: STEVENS Total Vertical Depth: 6850 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73154

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1150		WITH 25 SX CMT
CIBP		1505		
CIBP		6250		
PROD	5.5	6826	1800	WITH 950 SX CMT
SURF	8.625	1767		WITH 650 SX CMT

#222.63

Well Type: SWD UIC Docket No: D27981.0 Date/Time to Plug: 06/25/2007 10:00 AM

Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: STEVE EMICK Company: CHESAPEAKE OPERATING Phone:

Proposed Plugging Method: AT 1200' PUMP 15 SX GEL - 150 SX CMT - 300# HULLS. AT 690' CIRCULATE CMT TO SURFACE OR SET AT CIBP @ 1150' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 06/25/2007 2:00 PM

KCC Agent: JIM HOLLAND

Actual Plugging Report:

PULLED 1800' OF 5 1/2" CASING PRIOR TO BEING CONVERTED TO A DISPOSAL. 1ST PLUG SET CIBP @ 1150'. RUN TUBING TO 1149' & PUMP 25 SX CMT. 2ND PLUG PULL TUBING TO 900' & CIRCULATE CMT TO SURFACE WITH 215 SX CMT. 3RD PLUG PULL OUT OF HOLE WITH TUBING. FILL 8 5/8" WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6752	6780		
6290	6300		
4281	4285		
1190	1230		


INVOICED

DATE 7-16-07
INV. NO. 2008060119

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

District: 01



Signed

Jim Holland
A.P.T. III
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 13 2007

CONSERVATION DIVISION
WICHITA, KS

Form CP-278