

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

KCC PKT  
7/19/07  
per OP

API Well Number: 15-055-00318-00-00  
Spot: SWSWSWNE Sec/Twnshp/Rge: 14-22S-34W  
2790 feet from S Section Line, 2490 feet from E Section Line  
Lease Name: NIQUITE Well #: 1  
County: FINNEY Total Vertical Depth: 2570 feet

Operator License No.: 32787  
Op Name: KANSAS NATURAL GAS OPERATING, I  
Address: PO BOX 818 1200 MAIN STREET  
HAYS, KS 67601

| String | Size  | Depth (ft) | Pulled (ft) | Comment         |          |
|--------|-------|------------|-------------|-----------------|----------|
| CIBP   |       | 1150       |             |                 | \$ 83.53 |
| CIBP   |       | 2465       |             | WITH 2 SX CMT   |          |
| PROD   | 5.5   | 2550       | 0           | WITH 150 SX CMT |          |
| SURF   | 8.625 | 317        |             | WITH 310 SX CMT |          |

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/20/2007 10:30 AM  
Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES  
Proposal Rcvd. from: STEVE LEHNING Company: KANSAS NATURAL GAS Phone: (620) 675-8185

**Proposed Plugging Method:** SET BRIDGE PLUG AT 2465. DUMP 2 SACKS OF CEMENT ON TOP PLUG. SET SECOND BRIDGE PLUG AT 1700' & DUMP 2 SACKS CEMENT ON PLUG. PERFORATE 5 1/2 CASING WITH 4 HOLES BETWEEN 1100'-1150'. PUMP CASING VOLUME WITH 60/40 POZ CEMENT FROM 1150' TO SURFACE AND TAIL WITH 80 SACKS OF CEMENT & 4 SACKS OF HULLS TO PLUG OFF PERFORATIONS. HOOK ONTO ANNULUS & HAVE 150 SACKS OF 60/40 POZ TO PUMP ON BACKSIDE. CUT CASING OFF 6' BELOW GROUND LEVEL TO COMPLETE PLUG JOB. KCC RECOMMENDATIONS BY MR. ERIC MCLUAREN OF DODGE CITY 05/08/07.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/22/2007 3:00 PM KCC Agent: KEN JEHLIK

**Actual Plugging Report:**

1ST PLUG SET CIBP @ 2465' & 2 SX CMT. 2ND PLUG SET CIBP @ 1150'. TEST CASING TO 400#. 3RD PLUG PERFORATE WITH 4 SHOTS @ 1125'. SQUEEZE WITH CMT RETAINER SET AT 1007'. PUMP 80 SX CMT. 4TH PLUG PULL TUBING OUT OF RETAINER. CIRCULATE CMT INSIDE 5 1/2" WITH 100 SX CMT. 5TH PLUG PUMP 45 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS. TEST TO 200#.

**Perfs:**


| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 2550 | 2570 | OH   |          |
| 2517 | 2524 |      |          |

**INVOICED**  
DATE 7-19-07  
INV. NO. 2008060146

Remarks: USED 60/40 POZMIX6% GEL BY HALLIBURTON.

Plugged through: TBG

District: 01



Signed Ken Jehlik

RECEIVED  
KANSAS CORPORATION COMMISSION  
(TECHNICIAN)

JUL 18 2007

CONSERVATION DIVISION  
WICHITA, KS

Form C-23  
per