

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20588-00-00
Spot: S2NENE Sec/Twnshp/Rge: 9-17S-31W
1070 feet from N Section Line, 640 feet from E Section Line
Lease Name: OHMART TRUST Well #: 1-9
County: SCOTT Total Vertical Depth: 4675 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 SOUTH MARKET STREET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
DVT		2392		WITH 355 SX CMT
PROD	4.5	4674	0	WITH 200 SX CMT
SURF	8.625	368		WITH 225 SX CMT

\$151.94

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/17/2007 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: LARRY KARLIN Company: LARIO OIL & GAS Phone: (316) 265-5611

Proposed Plugging Method: PUMP 40 SX CMT & 200# HULLS. GEL TO ANHYDRITE. CMT TO SURFACE. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/14/2007 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 40 SX CMT & 200# HULLS AT 4550'. PUMP 27 BBLs GEL. PUMP 160 SX CMT FROM 2500' TO 0'. PRESSURE TO 750#. HELD AT 600#. HOOK UP TO 4 1/2" X 8 5/8" ANNULUS & ATTEMPT TO PUMP IN TO AT 750#. COULD NOT. ANNULUS APPARENTLY FULL OF CMT.

Perfs:


Top	Bot	Thru	Comments
4545	4550		
4535	4537		
4022	4026		

INVOICED
DATE 7-19-07
INV. NO. 2008060147

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed

Ken Jehlik

(TECHNICIAN)
RECEIVED
KANSAS CORPORATION COMMISSION

JUL 18 2007

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

PPF