

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-21488-00-00  
Spot: N2SEW Sec/Twnshp/Rge: 25-27S-18W  
1650 feet from N Section Line, 1980 feet from W Section Line  
Lease Name: MILLER Well #: 5  
County: KIOWA Total Vertical Depth: 4850 feet

Operator License No.: 31929  
Op Name: T. T. PRODUCTION, INC.  
Address: RR 1, BOX 91  
HAVILAND, KS 67059

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4850	2487	WITH 200 SX CMT
SURF	8.625	415		

\$1 157.63

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/29/2007 8:50 AM

Plug Co. License No.: 30891 Plug Co. Name: LEIKER WELL SERVICE, INC.

Proposal Rcvd. from: GARY TAYLOR Company: T.T. PRODUCTION Phone: (620) 723-2944

Proposed Plugging Method: SAND BACK TO 4092' WITH 4 SX CMT. PLUG AT 1120' WITH 12 SX GEL & 50 SX CMT. PLUG AT 440' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN  
Date/Time Plugging Completed: 06/29/2007 10:05 AM

Witness Type: COMPLETE (100%)  
KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:


SAND BACK TO 4092' WITH 4 SX CMT ON TOP. 1ST PLUG AT 1120' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 440' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT. GOOD RETURNS, CMT CIRCULATED.

INVOICED  
DATE 7-16-07  
INV. NO. 2008060124

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED Form CP-2/3  
KANSAS CORPORATION COMMISSION

JUL 13 2007

CONSERVATION DIVISION  
WICHITA, KS

PKT