

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-16660-00-00
Spot: SWSW Sec/Twnshp/Rge: 19-32S-13W
660 feet from S Section Line, 660 feet from W Section Line
Lease Name: MILLS Well #: 1
County: BARBER Total Vertical Depth: 5046 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N. MARKET, SUITE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4440		WITH 2 SX CMT
PROD	5.5	4670	1100	WITH 100 SX CMT
SURF	13.38	255		WITH 250 SX CMT

164.00

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/03/2007 11:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: JOHN SWINFORD Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SET CIBP & 2 SX CMT @ 4440'. PLUG AT 600' WITH 15 SX GEL & 50 SX CMT. PLUG AT 280' WITH 100 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/03/2007 12:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4440' & PUT 2 SX CMT ON TOP OF PLUG THROUGH DUMP BAILER. LAID DOWN CASING. RUN 2 3/8" TUBING TO PLUG THROUGH. 1ST PLUG AT 630' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 100 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4560	4570		
4532	4538		
4490	4496		

INVOICED
DATE 7-16-07
INV. NO. 2008060127

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED Form CP-2/3
KANSAS CORPORATION COMMISSION

JUL 13 2007

CONSERVATION DIVISION
WICHITA, KS

PKT