

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-22095-00-00  
Spot: NWSWNESE Sec/Twnshp/Rge: 8-16S-25W  
1815 feet from S Section Line, 1155 feet from E Section Line  
Lease Name: BREIT Well #: 1  
County: NESS Total Vertical Depth: 4575 feet

Operator License No.: 5086  
Op Name: PINTAIL PETROLEUM, LTD.  
Address: 225 NORTH MARKET, STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4574	0	WITH 200 SX CMT
SURF	8.625	340		

\$148.69

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/18/2007 10:30 AM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: MIKE KERNS Company: PINTAIL PETROLEUM Phone: (316) 263-2243

Proposed Plugging Method: PUMP 200# HULLS & 40 SX HOT CMT AT 3100'. PLUG AT 1300' WITH 30 SX HOT CMT. PRESSURE TEST CASING. PERFORATE AT 1150'. IF PRESSURE TESTS, PUMP CASING VOLUME + 80 SX CMT. IF NOT, RUN TUBING TO 1100' & FILL WITH CMT. PUMP 150 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/18/2007 3:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

LEFT 1470' OF TUBING IN HOLE. HAD A CASING BREAK IN. WASHED OVER TUBING AND GOT TO 3100'. NO ALT 2 CEMENT. RAN TUBING TO 3100' & PUMPED 35 SX COMMON CMT WITH 3% CC. PULLED TUBING TO 1350' & PUMPED 60 SX COMMON CMT WITH 3% CC. WAITED 1 1/2 HOURS. PRESSURED CASING TO 500# & HELD. PERFORATED AT 1050'. TIED ONTO CASING AND PUMPED 170 SX CMT. DID NOT CIRCULATE. MAXIMUM PRESSURE 900#. SHUT IN PRESSURE 500#. TIED ONTO BACKSIDE & PUMPED 100 SX CMT. CMT CAME UP 12' FROM WELL HEAD. SHUT DOWN.


Perfs:

INVOICED  
DATE 7-11-07  
INV. NO. 2008060099

Remarks: USED COMMON CMT W/3% CC & 60/40 POZMIX 6% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01



Signed

*Michael Maier*

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION Form CP-238

JUL 09 2007

CONSERVATION DIVISION  
WICHITA, KS

*[Handwritten signature]*

*PFT*