

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22458-00-00
Spot: NWSESWSE Sec/Twnshp/Rge: 8-15S-25W
520 feet from S Section Line, 1780 feet from E Section Line
Lease Name: HOWARD Well #: 1
County: TREGO Total Vertical Depth: 4393 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE ROAD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	262		

\$142.77

Well Type: DH UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: ANDY Company: MURFIN DRILLING CO., INC. Phone: _____

Proposed 1st plug @ 1860' w/ 25 sacks.
Plugging 2nd plug @ 900' w/ 100 sacks.
Method: 3rd plug @ 300' w/ 40 sacks.
4th plug @ 40' w/ wiper plug and 10 sacks.
Rathole - 15 sacks.
Mouse hole - 10 sacks.

Plugging Proposal Received By: DAVID WANN WitnessType: NONE
Date/Time Plugging Completed: 07/05/2007 10:00 AM KCC Agent: DAVID WANN

Actual Plugging Report:

Hole reported plugged as above.
Order 200 sacks 60/40 pozmix w/ 6% gel and 1/4 lb flowcel per sack.

Perfs:

INVOICED
DATE 7-11-07
INV. NO. 2008060101

Remarks: CEMENTED BY ALLIED CEMENTING.

Plugged through: DP

District: 04

Signed _____

(TECHNICIAN)
RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

JUL 09 2007

CONSERVATION DIVISION
WICHITA, KS

JUL 06 2007

PKT