

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-24031-00-00  
Spot: N2N2NW Sec/Twnshp/Rge: 1-15S-19W  
4950 feet from S Section Line, 3960 feet from E Section Line  
Lease Name: PFANNENSTIEL Well #: 9  
County: ELLIS Total Vertical Depth: 3710 feet

Operator License No.: 6484  
Op Name: ANDERSON ENERGY, INC.  
Address: 221 S. BROADWAY, SUITE 302  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3703	0	w/150 sxs cmt
SURF	8.625	603	0	w/280 sxs cmt

**\$ 120.58**

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/26/2007 8:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: \_\_\_\_\_ Company: ANDERSON ENERGY, INC. Phone: (316) 263-1006

Proposed Plugging Method: Ordered 375 sxs 60/40 pozmix - 10% gel - 800# hulls.  
Backside full.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/26/2007 12:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

RTI to 2800' - pumped 125 sxs cement with 300# hulls.  
Pulled tubing to 1500' - pumped 110 sxs cement with 200# hulls - good circulation of cement.  
Pulled out tubing - squeezed with 25 sxs cement.  
Max. P.S.I. 500#. S.I.P. 300#.  
Tied onto backside - was full.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

**INVOICED**  
DATE 7-11-07  
INV. NO. 2008060094

District: 04

*HD.*

Signed

*Marvin Mills*

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-2/3


JUL 09 2007

JUL 03 2007

CONSERVATION DIVISION  
WICHITA, KS

*PAT*

THORNTON E. ANDERSON  
 840 FIRST NAT'L BANK BLDG. #9 PFANNENSTIEL 1-15-19W  
 WICHITA, KS 67202 C N/2 N/2 NW  
 CONTR MALLARD DRILLING CO. CTY ELLIS  
 GEOL JOHN CARNES FIELD DECHANT WEST  
 ELV 2111 KB<sub>SPD</sub> 9/25/84 CARD ISSUED 12/6/84 IP P 35 BOPD, NW  
ARB OH 3707-3710



LOG	Tops	Depth/Datum
TOP	.....	3070- 959
KH	.....	3205-1094
QH	.....	3264-1153
HEEB	.....	3348-1237
TOR	.....	3367-1256
LANS	.....	3392-1281
BKC	.....	3641-1530
ARB	.....	3703-1592
RTD	.....	3704-1593
LTD	.....	3710-1599

API 15-051-24,031  
 8 5/8 " 603.43/280SX, 5 1/2 " 3703/150SX  
 DST (1) 3224-41 (PENN) / 30-45-30-45, REC 65' MW, SIP 885-783#, FP 45-45 / 57-57#  
 DST (2) 3302-3410 (PENN) / 30-45-45-45, REC 120' M, SIP 1157-1099#, FP 102-102 / 136-136#  
 DST (3) 3550-70 (LKC) / 30-45-30-45, REC 200' M, SIP 975-828#, FP 159-159 / 159-159#  
 MICT - CO, (ARB OH), BAILED 300' OIL/ 10", 500' OIL/ 15", 1000' OIL/ NEXT 20", SION, ONFU 3200' OIL, NW, T&R, POP, P 35 BOPD, NW 11/1/84

COPYRIGHT 1984  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS