

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-23145-00-00  
Spot: S2SWNW Sec/Twnshp/Rge: 36-33S-15W  
2167 feet from N Section Line, 651 feet from W Section Line  
Lease Name: OSAGE Well #: 106  
County: BARBER Total Vertical Depth: 1437 feet

Operator License No.: 32811  
Op Name: OSAGE RESOURCES, LLC  
Address: 6209 N K61 HWY  
HUTCHINSON, KS 67502

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	212		

\$ 46.70

Well Type: LH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/02/2007 8:30 AM  
Plug Co. License No.: 33724 Plug Co. Name: WARREN DRILLING, LLC  
Proposal Rcvd. from: BROOKE MAXFIELD Company: OSAGE RESOURCES Phone: (620) 664-9622

Proposed Plugging Method: 1ST PLUG AT 1200' WITH 50 SX CMT. TAG CMT. 2ND PLUG AT 620' WITH 150 SX CMT. 3RD PLUG AT 240' WITH 40 SX CMT. 4TH PLUG AT 60-0' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: PARTIAL  
Date/Time Plugging Completed: 07/03/2007 12:15 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:


1ST PLUG PUMP 50 SX CMT AT 1200'. WAITED 2 HOURS & TAGGED CMT AT APPROX. 1100'. 2ND PLUG AT 620' WITH 150 SX CMT. RAN 8 JOINTS DRILL PIPE IN. DID NOT TAG CMT. PULLED BACK OUT TO 620'. PUMPED 75 SX CMT. WAITED ON 2ND BULK TRUCK. PUMPED 150 SX CMT WITH 3% CC. TAGGED CMT AT 600'. 3RD PLUG AT 240' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG RATHOLE PLUGGED WITH 15 SX CMT.

INVOICED  
DATE 7-11-07  
INV. NO. 2008060097

Remarks: USED 60/40 POZMIX 6% GEL 2% CC 1/4# FLO SEAL BY JET STAR.

Plugged through: DP

District: 01



Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-233

JUL 09 2007

CONSERVATION DIVISION  
WICHITA, KS