

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-04918-00-00
Spot: NWSEW Sec/Twnshp/Rge: 1-11S-18W
3630 feet from S Section Line, 1650 feet from W Section Line
Lease Name: PARKER Well #: 2
County: ELLIS Total Vertical Depth: 3452 feet

Operator License No.: 30537
Op Name: VENTURE RESOURCES, INC.
Address: 2110 S. GILPIN PO BOX 101234
DENVER, CO 80250

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3439	0	w/200 sxs cmt
SURF	8.625	1195	0	w/340 sxs cmt

\$112.19

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/28/2007 1:30 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOHN CEARLY Company: VENTURE RESOURCES, INC. Phone: (303) 722-2899

Proposed Plugging Method: 03/28/2007 - Ordered 285 sxs Swift Multi Density Cement w/600# hulls.
07/02/2007 - Ordered 100 sxs 60/40 pozmix - 10% gel.
Top of tubing fish 2300' - unable to recover - decided to P/A.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/28/2007 4:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated two holes at 1150'.
Ran tubing to 1882'. Swift Services pumped 185 sxs w/300# hulls.
Pulled tubing to 945' - pumped 75 sxs SMD with 300# hulls - circulated cement out 5 1/2".
PTOH. Topped off with 25 sxs - casing full.
07/02/2007 - Witnessed by Pat Staab
Swift Services pumped 25 sxs 60/40 pozmix - 10% gel.
Max. P.S.I. 400#. S.I.P. 400#.

Perfs:

INVOICED
DATE 7-11-07
INV. NO. 2008060104

Remarks: LEASE ORIGINALLY KNOWN AS ETTA RIDDLER #2. SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

JUL 09 2007

CONSERVATION DIVISION
WICHITA, KS

JUL 05 2007

SKELLY OIL COMPANY #2 RIDDLER ^{AD} 1-11-18W
 NW SE NW

Contr. _____ ELLIS _____ County

E. 1910 Comm. 10-30-48 Comp. 12-31-48 IP 35 BOPD & 315 BW

Tops	Depth	Datum	Casing
ANH	1188	+722	8" 1195
HEEB	3091	-1181	5" 3441
LANS	3137	-1227	
CONG	3385	-1475	
SIMP SH	3426	-1516	
SIMP DOL	3430	-1520	
ARB	3440	-1530	
T.C.	3452	-1542	

850' OIH/2 HRS: ACID 1000:
 SWB 25 BO & 225 BW/10 HRS:
 PB 3449: PMP 117 BO & 282 BW/10 HRS
 PB 3446: PERF 35 S, 3443-46:
 ACID 200: CO 3448: PERF 24 S, 3446-48
 ACID 400: SWB 6 BO & 14 BW/3 HRS:
 PERF 46 S, 3431-35
 ACID 500
 PMP 85 BO & 34 BW/21 HRS:
 PLUG 3436

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

