

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-21934-00-00  
Spot: SESWSE Sec/Twnshp/Rge: 22-11S-22W  
330 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: SHUBERT A Well #: 2  
County: TREGO Total Vertical Depth: 3970 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, INC.  
Address: PO BOX 438  
HAYSVILLE, KS 67060

| String | Size  | Depth (ft) | Pulled (ft) | Comment       |
|--------|-------|------------|-------------|---------------|
| PROD   | 4.5   | 3968       | 0           | w/340 sxs cmt |
| SURF   | 8.625 | 262        | 0           | w/170 sxs cmt |

\$ 129.03

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/05/2007 3:00 PM  
Plug Co. License No.: 33346 Plug Co. Name: TR SERVICE AND RENTAL, INC.  
Proposal Rcvd. from: DICK SCHREMMER Company: BEAR PETROLEUM, INC. Phone: (316) 524-1225

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 400# hulls.  
Check backside.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/05/2007 5:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing in to 2100' - pumped 150 sxs cement with 400# hulls - good circulation of cement.  
Pulled tubing out - tied onto top and squeezed with 25 sxs cement.  
S.I.P. 300#.  
Tied onto backside with 10 sxs cement.  
S.I.P. 300#.

Perfs:

Remarks: COPELAND CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

Form CP-2/3

JUL 11 2007

CONSERVATION DIVISION  
WICHITA, KS

JUL 06 2007

PJT

STRATA ENERGY RESOURCES CORPORATION  
NEWPORT BEACH, CA 92660

22-11 -22W  
SE SW SE

#2 SHUBERT

site: 2-1/2 N & 6-3/4 E OF WAKEENEY, KS

city: TREGO

API 15-195-21934

contr: REVLIN DRILLING, INC

field: GAGELMAN SO.

geol: BETH FUHR

fr date 09/11/87 spd date 10/01/87 drig comp 10/09/87 card issued 04/06/88 last revised 04/06/88

|  |  |  |  |
|--|--|--|--|
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |

ELV: 2272 KB LOG  
tops.....depth/datum  
ANH.....1715 +557  
TOP.....3286 -1014  
HEEB.....3497 -1225  
TOR.....3522 -1250  
LANS.....3538 -1266  
BKC.....3570 -1298  
MARM.....3853 -1581  
ARB.....3961 -1689  
RTD.....3970 -1698

IP status:

OIL, P 25 BOPD, NW, MARM 3866-3876,  
CSG: 8-5/8" 262 / 170 SX, 4-1/2" 3968 / 340 SX  
NO CORES  
DST (1) 3587-3605 (PENN), / 30-30-30-60, REC 3' DM  
ISIP 36# FSIP 36# IFP 36# -36# FFP 36# -36# IHP  
1894# FHP 1874# BHT 109 "

(over)

COPYRIGHT 1988  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

STRATA ENERGY RESOURCES CORPORATION  
NEWPORT BEACH, CA 92660

22-11 -22W  
SE SW SE

#2 SHUBERT

DST (2) 3617-3632 (PENN), / 60-60-60-90, REC 240' MW, W / SO ON TOP ISIP 494# FSIP  
494# IFP 36# -73# FFP 109# -128# IHP 1894# FHP 1874# BHT 110 "  
MICT - CO, PF (MARM) 3866-3876, W / 2 SPF, FRAC'D (AMT NA), GSO, SET 2-3/8" TBG AT  
3888, POP, P 25 BOPD, NW (GR 36), 10/23/87