

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-00940-00-01
Spot: SWNWSW Sec/Twnshp/Rge: 35-14S-21W
1650 feet from S Section Line, 4950 feet from E Section Line
Lease Name: HOLTSINGER Well #: 2
County: TREGO Total Vertical Depth: 3840 feet

Operator License No.: 5010
Op Name: KNIGHTON OIL COMPANY, INC.
Address: 221 S. BROADWAY, STE. 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3760		
PROD	7	3835	0	175 SX
SURF	10.75	229	0	150 SX

\$ 124,80

Well Type: EOR UIC Docket No: E13935.2 Date/Time to Plug: 07/06/2007 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: KEN WERNER Company: KNIGHTON OIL COMPANY, INC. Phone: (785) 623-4081

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 10% gel - 800# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/06/2007 12:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing into 3573' - pumped 40 sxs cement with 350# hulls.
Pulled tubing to 3223' - pumped 80 BBLs drilling mud.
Pulled tubing to 1425' - pumped 185 sxs cement with 250# hulls - circulated to surface.
Pulled tubing out - filled down the top with 20 sxs cement - no squeeze.
Backside full of cement.

Perfs:

Top	Bot	Thru	Comments
3803	3809		
3791	3797		
3783	3786		
3740	3746		
3726	3734		
3466	3476		

INVOICED
DATE 7-12-07
INV. NO. 2008060109

Remarks: ALLIED CEMENTING COMPANY-TICKET #21194.

Plugged through: TBG

District: 04

Signed *Marvin Mills*

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

JUL 11 2007

CONSERVATION DIVISION
WICHITA, KS

JUL 09 2007

PST

MID-CONTINENT, PETROLEUM

#2 HOLZINGER

35-14-21W
SW NW SW

Contr. _____ TREGO _____ County

E 2056^{RB} Comm. _____ Comp. 11-12-54 IP 22 BO / 6 BWPD

Tops	Depth	Datum
HEEB	3345	-1289
LANS	3389	-1333
MARM	3718	-1662
CONG	3781	-1725
ARB	3823	-1767
TD	3840	-1784

Casing

10" 229 OW WO

7" 3839

OLD INFOR: DST 3769-3810/1 HR


315' 0 & GCM, BHP 710#

PERF 3803-09: 3791-97: 3783-86

NEW INFOR: FRAC: PERFS OPEN:

NEW POT, 22 BO / 6 BWPD

GROFF POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS