

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23435-00-00
Spot: W2W2SW Sec/Twnshp/Rge: 22-12S-15W
1210 feet from S Section Line, 410 feet from W Section Line
Lease Name: VONLINTEL Well #: 2
County: RUSSELL Total Vertical Depth: 3340 feet

Operator License No.: 6246

String Size Depth (ft) Pulled (ft) Comment

Op Name: BENNETT & SCHULTE OIL CO., A General SURF 8.625 210

Address: 140 WEST WICHITA AVE.
RUSSELL, KS 67665

Partnership

\$ 108.55

Well Type: DH

UIC Docket No:

Date/Time to Plug: 06/02/2007 1:00 PM

Plug Co. License No.: 33905

Plug Co. Name: ROYAL DRILLING INC

Proposal Rcvd. from: DOUG BUDIG

Company: BENNETT & SCHULTE OIL COMPA Phone: (785) 483-2721

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS

Witness Type: NONE

Date/Time Plugging Completed: 06/03/2007 12:15 AM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

1st. Plug at 3242' w/25 sxs.
2nd. Plug at 900' w/40 sxs.
3rd. Plug at 446' w/80 sxs.
4th. Plug at 260' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

INVOICED

DATE 7-26-07

INV. NO. 2008060184

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Richard Williams

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

JUL 25 2007

JUL 17 2007

CONSERVATION DIVISION
WICHITA, KS

AT